CR-SHE: One-round, tamper-evident range analytics over encrypted, replicated IoT data under $(n-1)$-collusion

ARTICLE INFO

Keywords:
Range aggregation
Distributed point function
Homomorphic encryption
Internet of Things
Multi-cloud
Summed-area table
Verifiable computation

ABSTRACT

Hiding which records an encrypted IoT query touches is worthless if aggregating over them hands the matched set back to the servers. We present CR-SHE, which answers multi-dimensional range aggregates over data encrypted under one owner's key and replicated to n providers, in one round without communication between providers, hiding the range, the matched records, their number and the result from any coalition of up to $n-1$ semi-honest providers. The owner stores encrypted summed-area tables of registered data cubes; a query is 2^d distributed-point-function keys with signed outputs at the box's corners, padded with dummy keys, and each provider returns one ciphertext. A second key set carries a secret scalar chosen afresh for every query, so an honest client accepts a wrong answer with probability about 2^{-36} whatever deviating providers compute, with no stored MAC key and no extra homomorphic work. Role-scoped columns and mask keys confine each user to its own role's records. On two real IoT corpora totalling 825,554 records a C++ prototype answers single-keyword aggregates in 39 ms per provider. On range cubes built from both corpora, a reference implementation answers a verified box query in 0.68–1.19 s per provider with one 132 kB response, flat from one minute or day to the whole timeline, and no wrong answer was accepted in 4,500 tampered trials. A verified query uploads 5,520 bytes per provider, against a computed 44 MB for a plain single-server baseline.

1. Introduction

The proliferation of connected sensors, wearables and cyber-physical systems has made the Internet of Things (IoT) one of the largest and fastest-growing sources of continuously generated data [1]. Bedside monitors, smart meters, traffic and environmental sensors and industrial controllers emit measurements continuously, and the people who need to query them, among them clinicians, grid operators, city agencies and maintenance contractors, are rarely the ones who own the devices. The natural response is to serve this data from the cloud, and modern deployments increasingly replicate it across several providers. Multi-cloud operation supplies elastic query capacity, improves availability through redundancy across independent infrastructures, and frees data owners from single-vendor lock-in [2, 3]. Yet much of this data is acutely sensitive, including physiological telemetry in connected healthcare, mobility traces in smart cities and diagnostic streams from connected vehicles, so it must be encrypted before leaving the IoT trust domain and stay encrypted in the cloud, even as multiple stakeholders need to query and analyse it.

Encrypting outsourced data with conventional schemes neutralises the reason it was sent to the cloud. A provider holding only ciphertexts can neither locate the records a query needs nor compute over them, forcing either decryption in the cloud, which reintroduces exposure, or a wholesale download to the client, which defeats the purpose of outsourcing. Searchable encryption lets a provider identify records matching an encrypted keyword [4–6], and leveled homomorphic encryption lets it evaluate bounded-depth arithmetic directly on ciphertexts [7, 8]. Both, in their single-server form, leak the access pattern, and a substantial body of leakage-abuse work converts that leakage into plaintext recovery [9–11].

Replicating data across independent providers offers an escape that single-server cryptography cannot. If the client splits its query so that no provider sees it, the access pattern stays hidden as long as one provider abstains from collusion. Splinter [12] established this model with function secret sharing, DORY [13] brought it to encrypted documents, and Waldo [14] extended it to rich predicates over time series. The model is therefore not new. What remains open is narrower: moving from private selection to encrypted, multi-dimensional range analytics without handing the selection back to the servers.

Selection and computation are not the same problem, and hiding the first is worthless if the second gives it back. A scheme can privately determine which records match a keyword and then, in order to aggregate over them, hand the matched index set to the providers, at which point the coalition learns the access pattern exactly, and across repeated queries the search pattern. We call this the *selection-to-computation composition leak*. Existing distributed-trust systems avoid it by not computing at all (DORY), by computing over data the servers can already read (Splinter, whose databases are public), by moving to a three-party honest-majority setting with secret-shared data and server-to-server interaction (Waldo), or by evaluating predicates over Shamir shares of unary-encoded values without server interaction (Obscure [15, 16]), where multiplying shares raises the polynomial degree, so that a one-round query needs $2l + 1$ servers for a predicate of length l, and the adversary must not control a majority of them [16, §2.1, §3.2]. Multi-cloud IoT deployments add three constraints that together define our setting: (i) privacy must hold while any one provider is honest, $t = n - 1$; (ii) providers never talk to one another, so there are no cross-cloud channels, synchronisation or egress charges; and (iii) the data are encrypted once under the owner's key, so a replica can be added, lost or revoked by copying ciphertexts, without re-dealing shares. These constraints rule out the obvious alternative of secret-sharing the data at $t = n - 1$, because a shared store cannot answer a hidden query without either server interaction or a single-server private-retrieval primitive (Section 5.2).

IoT analytics are range queries. A clinician asks for one patient's mean heart rate across a night, a city agency for the number of hours carbon monoxide sat in its top three bands at one site, a maintenance contractor for a machine's vibration total over a shift. Each is an aggregate over a box in a small number of ordered dimensions: device, time window, value band. Answering such a box with single-keyword aggregates costs one query per tag in the box and reveals its length; retrieving the records first costs a retrieval per tag and hands the client data it did not ask for. Prior distributed-trust systems that support ranges compute over plaintext or need an honest majority with interaction (Section 2), and single-server encrypted range aggregation leaks access patterns or evaluates homomorphic comparisons.

We propose CR-SHE (Collusion-Resilient Searchable Homomorphic Encryption). The data owner replicates a one-time-pad-masked pseudonymous index and a homomorphically encrypted record column to n providers. A registered single-keyword query sends one distributed point function (DPF) key per provider, and a registered d-dimensional range sends 2^d. Rather than returning the selection vector so the client can name the matched records, each provider contracts its *own share* of that vector against owner-encrypted columns and returns a single ciphertext; the client adds the n ciphertexts and decrypts once. The matched set is never assembled at any provider, its cardinality never leaves the client, and per-query downlink for an aggregate is one ciphertext rather than linear in the record count. The contributions are as follows.

- **One-round oblivious range aggregation** (Section 5.7). The owner registers data cubes over ordered tag families and stores encrypted summed-area tables. A d-dimensional box query is 2^d DPF keys with signed outputs at its corners, padded with zero-output dummy keys so that ranges touching the cube's edge are indistinguishable, and each provider returns one ciphertext. Provider work and the response are independent of the range and of the record count; cost is linear in the cube's size.

- **Tamper evidence from a per-query secret** (Section 5.8, Theorem 2). Each column's second slot row holds a copy of its first, and the client sends a second key set whose outputs carry a fresh secret scalar δ_s. Whatever a coalition of providers computes, the client accepts a changed answer with probability at most $1/(p - 1)$ plus the DPF advantage, on every path: single keyword, range and the flexible path. No MAC key is stored, the homomorphic work is unchanged, and the deviations that per-row and per-cell keys miss, those aimed at the queried point, are caught. A one-time MAC key chosen by the client already appears in two-server decision-tree evaluation [17], delivered under homomorphic secret sharing; what is specific here is carrying it inside the DPF outputs, at no public-key or homomorphic cost, and an argument that covers coalitions of up to $n - 1$ providers.

- **Role-scoped access without interaction** (Section 5.9). A user of one role holds only that role's mask key, so retrieval reveals membership bits of its own records and leaves the rest one-time-padded; its aggregate columns, cube tables and record column are built from its records only, so no vector it sends reaches another role's data. Providers apply a role-to-column policy and nothing else. This turns the authorisation gap of our earlier design into a stated mechanism, at a storage cost per role.

- **The composition leak, and the cost of avoiding a homomorphic layer at $t = n - 1$.** Proposition 1 shows that local answers over (n, n) additive shares miss cross terms, and that a non-interactive repair with data-independent queries, correct on every share tuple, yields single-server private information retrieval, hence oblivious transfer. This is not a lower bound for every secret-sharing design: threshold sharing at a lower collusion bound, preprocessing or interaction escape it, and the homomorphic layer is our design choice at $t = n - 1$.
- **The single-keyword fast path, packing and a flexible path.** Registered single-keyword templates cost a symmetric full-domain pass plus $O(N/\ell)$ packed ciphertext operations, independent of the record count, with several templates in the two slot rows of one ciphertext; a two-round flexible path serves conjunctions and ad-hoc weights; the masked membership index is one-time-padded and packed 32 bits per word, an engineering step that cuts it 32-fold. The algebraic compatibility condition (Lemma 1) under which DPF shares and the homomorphic plaintext ring compose is made explicit.
- **Evaluation and its scope.** A C++ prototype measured the single-keyword path, a single-host multi-provider deployment, six baselines and a leakage-abuse attack on two real IoT corpora totalling 825,554 records and 46,742 tags. A reference implementation measures range aggregation on cubes built from both corpora and on a synthetic cube, all three verification modes against five injected deviations (4,500 session-check trials), the role-scoped extraction attack and the packed index, and reruns correctness and the leakage attack, now with power-of-two and volume-hiding baselines, on both corpora (Section 9). A native port of the range path and a cross-region deployment remain to be measured.

The remainder of this paper is organised as follows. Section 2 reviews related work. Section 3 fixes notation and primitives. Section 4 presents the system and threat model. Section 5 details the construction, Section 6 the security analysis, and Section 7 the asymptotic costs. Section 8 describes the implementation, Section 9 reports and discusses results, and Section 10 concludes.

2. Related work

2.1. Distributed-trust query systems

Splinter [12] established the model of splitting a query into function-secret-sharing shares evaluated against replicas, hidden as long as one provider abstains, with SUM, COUNT, MAX and TOPK over *public* cleartext databases. Its conditions are equalities, intervals, and an AND of equalities with at most one interval [12, Fig. 4], so it answers one-dimensional range aggregates over public data; its providers are honest-but-curious, and it does not protect against incorrect results [12, §2.3]. DORY [13] moves to encrypted documents: ℓ replicas ($\ell = 2$ in its implementation) hold a Bloom-filter index whose bits are one-time-padded with a PRF of a per-folder key and the document version [13, §4.1]; it hides search access patterns, including the number of results, from an attacker that maliciously controls $\ell - 1$ of the ℓ trust domains, and proves security with abort using aggregate MACs [13, §3.4, §4.3]. It stops at retrieval. Waldo [14] supports multi-predicate filtering over time series with malicious security, in a three-party honest-majority setting with secret-shared data and server-to-server interaction, that is, a collusion bound of $t = 1$. CR-SHE trades Waldo's predicate expressiveness and full malicious security for $t = n - 1$, no inter-provider communication and owner-keyed encryption at rest. Obscure [15, 16] is the closest system we found: count, sum, average, maximum and top-k queries with conjunctive or disjunctive equality predicates over Shamir secret-shared, unary-encoded data at $c > 2$ non-communicating servers, hiding access patterns, query patterns and output sizes, with information-theoretic security, data from one or several owners, and optional result verification against malicious servers [16, §1, §3]. Its adversary may not collude with all, or possibly a majority, of the servers [16, §3.2]. String matching multiplies shares, so a predicate of length l evaluated in one round needs $2l + 1$ shares [16, §2.1, Table 7]: in its experiments a one-attribute count over six-digit values needs thirteen servers and a three-attribute disjunction twenty-five, and with fewer servers the user interpolates partial results or adds a round [16, App. E]. Range queries are rewritten as point queries, or as a few node values of a k-way tree that the owner precomputes as extra attributes; experiments cover one-dimensional count and sum, and the same decomposition is said to extend to conjunctive and disjunctive queries [16, §8.3, §9]. Against it CR-SHE offers $t = n - 1$ for any $n \geq 2$, with $n = 2$ sufficing, and d-dimensional box

aggregates with a fixed 2^d keys per box, over replicas encrypted once under the owner's key; Obscure offers information-theoretic security, several owners, and richer query types. The primitives are due to Gilboa and Ishai [18] and Boyle, Gilboa and Ishai [19, 20]; FSS also serves metadata-hiding messaging [21], robust private statistics [22, 23], access control for dealers [24] and verifiable keys [25]; fast FSS-based secure computation [26] and DPF-based ORAM for secure computation [27] are complementary to the ciphertext-side contraction below. At bottom, DPF-based selection is multi-server PIR [28], and its linear server work is the price of PIR without preprocessing [29]; what CR-SHE adds is the ciphertext-side contraction with key-carried session verification, the packed masked index, and one-round prefix-sum range cubes.

2.2. Private range aggregation

Prefix sums answer a range sum from a constant number of lookups, a structure known from data cubes [30] and summed-area tables [31]. Boyle, Gilboa and Ishai obtain function secret sharing for d-dimensional intervals with key size $O(\lambda n^d)$ for n-bit coordinates by reducing a box, through inclusion–exclusion, to 2^d intervals anchored at zero [20, Cor. 3.4]; the decomposition our range path uses is therefore theirs, applied on the data side rather than the function side (Section 5.7). Over encrypted data held by one server, ARQ [32] builds range sums, minima, modes and medians from structured encryption, primarily for one-dimensional queries; its strongest notion, data obliviousness, still lets the query leakage depend on the query itself [32, Def. 3.3], and its range-sum scheme follows Demertzis et al.'s prefix sums [33]. HADES [34] is a one-round, two-party protocol in which the analyst encrypts only the query parameters under BFV, and a single data provider holding its database in cleartext computes encrypted indicator vectors for point and range predicates, combines them with AND, OR and NOT, and aggregates, so that it learns neither the selection nor the result [34, §2–§3]. A conjunction of ranges over several columns gives box aggregates, at a cost linear in the number of records; its efficiency comes from evaluating predicates against plaintext values, and its threat model concerns the privacy of query parameters, without result verification [34, §2.3]. HADES therefore covers the public-data case that CR-SHE does not, and CR-SHE the owner-encrypted case that HADES does not. With non-colluding servers, Hayata et al. [35] give FSS-based PIR for range *retrieval*; in Hafiz et al. [36] each of ℓ servers hosts a plaintext copy of the database and multiplies the client's Shamir-shared query vector by precomputed indexes of aggregate queries (sum, count, mean, min/max, histograms) in one round, private against t colluding servers when $t+1$ respond, so t can reach $\ell-1$, with a v-Byzantine-robust variant [36, §II, §VI-C, App. B]; filters select indexed values, and range predicates are not among the queries it describes; and Waldo [14] supports range predicates over secret-shared time series with an honest majority and server interaction. CR-SHE's range path instead composes prefix-sum data cubes with oblivious homomorphic contraction, so that the data remain encrypted at rest under the owner's key, the coalition bound is $t = n-1$ for any $n \geq 2$, and providers answer d-dimensional box queries in one round without interacting. Neither private aggregation nor prefix-sum range queries is new in isolation, and function secret sharing for multi-dimensional intervals exists [20]; the contribution is the combination. We have read Splinter, DORY, ARQ, PVODTE, Obscure, Hafiz et al., HADES and the FSS constructions of Boyle et al.; our characterisation of Hayata et al. and SHAMC rests on their abstracts, and a search reaches only what it can open, so we make no claim of priority; the search log ships with our artefact.

2.3. Verification and access control for hidden queries

Verifiable DPFs [25] and access control for FSS [24, 37] let servers check that a client's *keys* are well formed or authorised; they guard against a malicious client. Against malicious servers, DORY keeps per-bit MAC tags condensed into aggregate MACs [13, §4.3], verifiable homomorphic secret sharing [38] checks evaluation, and PVODTE [17] has the client generate a one-time MAC key, encrypt it under homomorphic secret sharing and send it to two servers, which return the result alongside its product with the key [17, §VII-B]; PVODTE is secure against one malicious server and leaves verifiability against colluding servers to future work [17, §IV-D]. Our tamper evidence is the same kind of information-theoretic MAC, value y alongside $\delta_s y$ as in SPDZ [39], with δ_s drawn afresh per query; it differs in carrying δ_s inside the DPF outputs, so the providers' stored state holds no key and no public-key operation or extra homomorphic product is needed, and in an argument (Theorem 2) that covers coalitions of up to $n-1$ providers. Our role-scoped access restricts which *data* a query can reach rather than which keys are accepted, and needs no proof or server-to-server message; it pays in storage per role.

2.4. Private information retrieval

PIR with preprocessing breaks the linear lower bound: offline hints let the online phase run in sublinear time, with two servers [40] or one [41, 42]. Those hints are client state computed over the whole database and invalidated by updates, which suits a stable table read by one client better than a stream ingested continuously and queried by many stateless data users; we keep the linear pass and list preprocessing as future work. Single-server PIR from lattice-based encryption [43–46] removes the non-collusion assumption altogether [47]. For the fast path in isolation it is a genuine alternative, being a PIR query into a table of owner-encrypted aggregates, and we measure it directly as baseline (vi) (Section 5.6): on that path one CR-SHE provider does less work than the single server but two providers together do not, and the trust split saves three to four orders of magnitude in uplink and 27–109 times in client computation, not asymptotic work. On retrieval and the flexible path a single server must multiply an encrypted selection vector by the whole $N \times N_d$ index, at least $N\lceil N_d/32\rceil/\ell$ homomorphic products with the same bit packing, which we bound at 1.5–3.1 times CR-SHE's retrieval in the same implementation; again a constant factor, with the uplink gap on top.

2.5. Encrypted search, encrypted analytics and multi-cloud storage

Searchable encryption leaks search and access patterns, which leakage-abuse attacks turn into plaintext recovery [9–11]; mitigations include ORAM [48], volume-hiding structured encryption [49, 50], which on heavy-tailed IoT postings is costly when it pads every list to the longest (by $N \max_x |I[x]|$ over the total postings, 1,285× for our primary corpus and 752× for the second, computed from the corpus statistics of Section 8), multi-cloud variants [51, 52] and richer or committee-authorised search [53–55]. Leveled homomorphic encryption [7, 8] underpins encrypted IoT analytics [56, 57]; Timecrypt [58] and Zeph [59] aggregate encrypted time series but reveal the queried interval. IoT search has been studied for sensing platforms [60] and vehicles [61], and multi-owner analytics with MPC and HE [62]. Multi-cloud storage designs disperse trust with hybrid encryption, secret sharing or attribute-based control [63, 64], or compute across clouds with partial HE [65]; systematisations note the lack of standard trust models [66]; and encrypted databases [67–69] rely on a trusted proxy or hardware rather than on non-colluding providers.

3. Preliminaries

This section fixes notation (Table 2) and recalls the primitives CR-SHE combines: a pseudorandom function for the index mask, additive secret sharing, distributed point functions for private selection across the replicated index, and leveled homomorphic encryption for aggregation on ciphertexts.

Pseudorandom functions. $F : \{0,1\}^\lambda \times \{0,1\}^* \to \{0,1\}^\lambda$ is a PRF if for every PPT distinguisher $\mathcal{B}$, $\mathbf{Adv}^{\mathrm{prf}}_{F,\mathcal{B}}(\lambda) = |\Pr[\mathcal{B}^{F_k(\cdot)} = 1] - \Pr[\mathcal{B}^{R(\cdot)} = 1]| \le \mathsf{negl}(\lambda)$ for a uniformly random key k and a truly random function R [70].

Additive secret sharing. An (n, n) additive sharing splits $m \in \mathbb{Z}_p$ into $(m_1, \ldots, m_n)$ with $\sum_j m_j = m$; any $n-1$ shares are uniform and independent of m.

Distributed point functions. An n-party DPF [18–20] for point functions $f_{\alpha,\beta} : [N] \to \mathbb{G}$ is a pair $(\mathsf{Gen}, \mathsf{Eval})$ with *correctness* $\sum_{j\in[n]} \mathsf{Eval}(j, \kappa_j, x) = f_{\alpha,\beta}(x)$ for all x, and $(n-1)$-*privacy*: a PPT simulator $\mathcal{S}_{\mathrm{DPF}}$ exists such that for every $C \subseteq [n]$ with $|C| \le n-1$, $\{\kappa_j\}_{j\in C} \approx_c \mathcal{S}_{\mathrm{DPF}}(1^\lambda, C, N)$. The two-party instantiation has keys of size $O(\lambda \log N)$ and admits full-domain evaluation in $O(N)$ pseudorandom-generator calls through a single traversal of the GGM tree, rather than the $O(N \log N)$ that N independent Eval calls would cost. For $n > 2$, succinct $(n-1)$-private constructions exist whose key size grows with both n and $\sqrt{N}$ [19]. Our prototype does not implement one: it instantiates $n > 2$ with a simpler sharing in which $n-1$ providers hold a λ-bit seed whose counter-mode expansion is their share, and one provider holds the explicit difference vector. That construction is correct by inspection and $(n-1)$-private under the PRF assumption: any coalition of $n-1$ providers is missing at least one seed expansion, which would hide α perfectly were it truly random, and is a PRF output in fact. Its per-provider key is λ bits for $n-1$ providers and $N\lceil \log p \rceil$ bits for one. This is not function secret sharing in the succinct sense, being the additive sharing of a unit vector familiar from multi-server PIR, so our key-size claims are for $n = 2$, and we use $n \in \{3, 4\}$ only to show that provider compute is flat in n; the uplink it costs is reported separately (Section 9.10).

Table 1
CR-SHE against distributed-trust query systems and encrypted-search baselines. *Oblivious analytics* means the servers learn neither which records feed the aggregate nor how many.

System	Storage at the servers	Search / filter	Oblivious analytics	Range aggregates	Collusion bound	Server channel	Malicious security	Hides $\lvert S\rvert$
Splinter [12]	plaintext replica	✓	○ (plaintext)	○ (1-D)	$n-1$	no	×	pad to k
DORY [13]	encrypted replica	✓	×	×	$n-1$	no	abort	✓
Waldo [14]	secret-shared	✓	✓	✓	1 (h. maj.)	yes	✓	✓
Hafiz et al. [36]	plaintext replica	✓	○ (plaintext)	×	$\ell-1$	no	○ (v-robust)	✓
Obscure [16]	Shamir-shared	✓	✓	○ (1-D tree)	minority	no	verify	✓
Timecrypt, Zeph [58, 59]	encrypted, 1 server	time only	✓	time, revealed	n/a	n/a	×	×
HADES [34]	public, 1 server	✓	○ (plaintext)	✓	n/a	n/a	×	✓
ARQ [32]	encrypted, 1 server	range	×	✓ (leaky)	n/a	n/a	×	×
Multi-cloud SSE [51]	encrypted	✓	×	×	×	no	×	×
Pattern-hiding SSE [52]	encrypted	✓	×	×	○	no	×	○
SHAMC [65]	encrypted	○	✓	?	×	yes	×	×
(n,n)-shared, local (§5.2)	secret-shared	✓	×‡	n/a	$n-1$	no	n/a	n/a
Single server, enc. selection	encrypted, 1 server	✓	✓	✓	none needed	n/a	×	✓
CR-SHE (this work)	encrypted replica	✓	✓	✓, 1 round	$n-1$	no	abort§	✓ / pad†

✓: supported; ○: partial; ×: not supported; ?: not determined, because for that work we have read only the abstract and search summaries. *Abort*: a deviating server is detected and the client aborts, without guaranteed output delivery; for DORY this is a proof of security with abort against malicious servers [13], for CR-SHE a correctness check alone (footnote §); *verify*, optional result verification; v-*robust*, robustness to v Byzantine servers, for Hafiz et al. (§VI-C there); *minority*, the adversary may not control a majority of the servers, and one-round queries need $2l+1$ servers for predicates of length l (Obscure, §2.1, §3.2). §Any provider deviation that changes the answer is caught except with probability about 2^{-36} (Theorem 2); no output delivery is guaranteed, and privacy is proved for semi-honest providers. †Aggregates hide $\lvert S\rvert$; retrieval pads to the public bound $k_{\max}$. ‡Local answers over additive shares miss the cross terms (Proposition 1); fixing that needs server interaction or a single-server PIR per share. The single-server row is baseline (vi): no non-collusion assumption, but an encrypted query linear in the domain (for a range query on our cube, about 44 MB against 5.5 kB of DPF keys with the verification key set).

Leveled homomorphic encryption. (KGen, Enc, Eval, Dec) is correct for arithmetic circuits of multiplicative depth $\le L_{\mathrm{HE}}$ over plaintext ring $\mathbb{Z}_p$ and IND-CPA secure with advantage $\mathbf{Adv}^{\mathrm{cpa}}$ [7, 8]. We write $\boxplus, \boxminus$ for ciphertext addition and subtraction and $\boxdot$ for plaintext-to-ciphertext multiplication, and use SIMD packing with ℓ slots. Providers hold only pk; sk never leaves the DO or DU. Opaque payloads use an IND-CPA symmetric scheme.

4. System and threat model

The **data owner** (DO), an IoT-domain authority such as a hospital, fleet operator or city data office, holds the tag dictionary D, the mask key K', the MAC keys and the HE secret key sk, and keeps the plaintext records in cold storage to precompute columns and rebuild tiers. **Producers** and **edge relays** generate and forward records and hold no secrets. The n **cloud providers** $\mathrm{CP}_1, \ldots, \mathrm{CP}_n$ each hold pk and a replica of the masked index and the encrypted columns and tables, and never decrypt. Authorised **data users** (DU) hold D, K' and delegated decryption, issue queries, and combine the providers' responses (Fig. 1). For example, a city's monitoring stations feed the data office, which replicates the encrypted store to three clouds; analysts at a health agency ask for the hours carbon monoxide spent in its top bands at one site last month, and no cloud learns the site, the month, the bands, the number of matching hours or the answer.

The adversary is probabilistic polynomial-time, static and semi-honest: it fixes a coalition $C \subseteq [n]$ with $|C| \le t = n-1$, whose members follow the protocol and pool everything they see, namely

$$\mathrm{View}_C = \big(I',\ \mathrm{CT},\ \widehat{\mathrm{CT}},\ pk,\ pp,\ \{A_f, \widehat{A}_f\}_f,\ \{T_f, \widehat{T}_f\}_{f,\mathrm{cube}},\ \{\kappa_{q,j}, v_{q,j}\}_{j\in C,\, q\in[Q]}\big),$$

plus the responses they compute, over adaptive queries. The goal is that this view be simulatable from data-independent leakage revealing neither the keyword or range, the access pattern, the result-set size, nor the result. The DO and authorised DUs are honest, channels are authenticated and confidential, and side channels beyond the message sizes accounted for here are out of scope. Beyond this semi-honest goal we address two

Table 2
Notation.

Symbol	Meaning
λ	security parameter
$n,\ t$	number of providers; collusion bound ($t = n - 1$)
$N,\ N_d$	index (tag) domain size; number of records
p	HE plaintext modulus; also the DPF output group
ℓ	number of SIMD slots per ciphertext
Q	number of adaptive queries
D	secret, append-only tag dictionary, $w \mapsto \alpha_w$
$F',\ K'$	PRF for the index mask; its key, fresh per static tier
$I,\ I'$	membership index in $\{0,1\}^{N \times N_d}$; masked index
P	one-time-pad mask, rejection-sampled from $F'_{K'}$, uniform on $\mathbb{Z}_p$
α_w	row of keyword w, $\alpha_w = D(w)$
b	record selection vector, $b = I[\alpha_w] \in \{0,1\}^{N_d}$
b_j	provider CP_j's additive share of $b + P[\alpha_w]$
$(\mathsf{Gen}, \mathsf{Eval})$	distributed point function (DPF)
κ_j	DPF key sent to provider CP_j
e_j	full-domain evaluation vector, $e_j[x] = \mathsf{Eval}(j, \kappa_j, x)$
$pk,\ sk$	HE public / secret key
$m_i,\ \mathsf{CT}_i$	computable field of record i; its ciphertext
$\delta,\ \widehat{\mathsf{CT}}_i$	MAC scalar; MAC column $\mathsf{Enc}(\delta m_i)$, in slot row 1
$\delta_x,\ K''$	per-row (per-cell) MAC key $F''_{K''}(x)$; its key
δ_s	per-query secret of the session check, uniform on $\mathbb{Z}_p^*$
$\rho,\ R,\ K'_\rho$	a role; number of roles; role ρ's mask key
$f,\ w_f$	aggregate template; its public weight vector
$A_f,\ \widehat{A}_f$	precomputed aggregate column; its MAC column
$v,\ v_j$	flexible selection vector over records; CP_j's share
$d,\ M$	cube dimension; number of cells $\prod_k s_k$
$C_f,\ T_f$	cell aggregates; their summed-area table
$\kappa_\sigma,\ \beta_\sigma$	corner $\sigma \in \{0,1\}^d$ of a box; its sign or 0
S	matched record set; $\lvert S\rvert$ its cardinality
$\mathcal{L}$	leakage profile
C	corrupted provider coalition ($\lvert C\rvert \le t$)
$\mathrm{DO},\ \mathrm{DU},\ \mathsf{CP}_j$	data owner; data user; j-th cloud provider

active threats. *Deviating providers* may return any response at all; the session check of Section 5.8 makes every deviation that changes an answer evident to the DU except with probability about 2^{-36} (Theorem 2), without guaranteeing output delivery. *Users exceeding their authority* may send malformed keys or arbitrary share vectors; role-scoped columns and mask keys confine a user to its own role's records (Section 5.9, Proposition 2). Collusion between a DU and a provider is excluded, since a DU already holds decryption capability, and a compromised DU exposes everything its role covers, since decryption is delegated in full.

5. The CR-SHE construction

5.1. Overview

The DO builds a membership index $I \in \{0,1\}^{N \times N_d}$ in which keyword w occupies row α_w and $I[\alpha_w][i] = 1$ if and only if record i contains w. Rows are assigned by a secret, append-only dictionary D: a keyword receives the next free row when it first appears and keeps it for the lifetime of the deployment, so rows never move




Figure 1: Overview of CR-SHE. The owner replicates a masked index and encrypted columns to n providers (1). A query is split into one DPF key per provider (2), each provider aggregates obliviously over its own share (3) and returns one ciphertext carrying value and MAC (4), and the user combines, verifies and decrypts (5). No provider ever sees the matched set or its size.

when keywords are added (Section 5.11). The DO shares D with authorised DUs and keeps it from the providers, because the vocabulary itself, being device and site names, is sensitive. Which row a keyword gets carries no security weight, since providers see neither addresses nor unmasked rows; only injectivity matters, for correctness. Rows are fixed width, so no row is distinguishable by size, and the index is stored masked as $I'[x][i] = I[x][i] + P[x][i] \bmod p$ with P drawn from the PRF $F'_{K'}$ by rejection sampling, so that every entry is uniform on $\mathbb{Z}_p$ (Section 5.4). The computable field of each record is encrypted as $\mathrm{CT}_i = \mathsf{Enc}_{pk}(m_i)$, with a MAC column $\widehat{\mathrm{CT}}_i = \mathsf{Enc}_{pk}(\delta m_i)$; opaque payloads are encrypted symmetrically.

A design that first recovers the selection vector at the client and then asks the providers to evaluate f over $\{\mathrm{CT}_i\}_{i\in S}$ destroys in the second step exactly what the first protected, because the providers are handed S. CR-SHE therefore never materialises S at a provider. Each provider contracts its own share of the selection vector against the encrypted column and returns one ciphertext. Algorithms 1 and 2 summarise the owner outsourcing procedures and the per-query protocol.

5.2. Why a homomorphic layer at $t = n - 1$

The obvious alternative to replicating ciphertexts is to deal the data to the providers as an (n, n) additive sharing over $\mathbb{Z}_p$ and answer DPF queries over the shares, with no homomorphic encryption at all. Under our constraints it does not work, and the reason fixes what any design here must contain.

Proposition 1 (No local answers over shares). *Let a column $A \in \mathbb{Z}_p^N$ be dealt as $A = \sum_{k\in[n]} S_k$, with $S_1, \ldots, S_{n-1}$ uniform and CP_k holding S_k, and let e_j be the evaluation vector of DPF key κ_j for $f_{\alpha,1}$. If each provider returns $r_j = \langle e_j, S_j\rangle$, then*

$$\sum_j r_j - A[\alpha] \;=\; -\sum_{j\neq k}\langle e_j, S_k\rangle,$$

and for $n = 2$, whenever $e_1 \neq e_2$, this error is uniform on $\mathbb{Z}_p$ over the choice of S_1, so the answer is correct with probability $1/p$; $e_1 = e_2$ occurs only with negligible probability.

Proof. $A[\alpha] = \langle \sum_j e_j, \sum_k S_k\rangle = \sum_{j,k}\langle e_j, S_k\rangle$; the providers' answers supply only the diagonal. For $n = 2$, substituting $S_2 = A - S_1$ gives the error $-\langle e_1, A\rangle + \langle e_1 - e_2, S_1\rangle$, which is uniform because S_1 is uniform and independent of the keys, provided $e_1 \neq e_2$. Equality would mean $e_1 = e_2 = 2^{-1}u_\alpha$; a provider could test its own share for that form and read α, so by $(n-1)$-privacy equality has negligible probability. □

The cross terms are not an artefact of choosing linear answers. Take any non-interactive scheme in which CP_1 holds an additive share S_1 of the data, the client forms its queries without reference to the data, providers answer independently, and every query and response is shorter than a share. Given a database X held by a single server, a client can run that scheme with $S_1 := X$ and the other shares drawn by itself, which fixes the data as $A = X + \sum_{k>1} S_k$. It plays providers $2, \ldots, n$ locally, sends only the first query to the server, and subtracts $\sum_{k>1} S_k[\alpha]$ from the result. Privacy against the single provider CP_1 hides α from the server, so this is a non-trivial single-server PIR scheme for X, and such schemes imply oblivious transfer [71]; their standard instantiation is homomorphic encryption [47]. Within that class, secret-sharing the data does not remove the public-key primitive, it moves it into a per-share PIR; the alternatives are interaction, for example multiplication triples, which the no-channel constraint excludes, or assumptions outside the class, such as preprocessing. The reduction does not show that every secret-sharing system needs homomorphic encryption. The argument needs the scheme to be correct on every tuple of shares, which holds for any scheme whose answers are a deterministic function of the shares and the queries, and it applies at $t = n - 1$ with (n, n) sharing. A lower threshold escapes it: with $(t{+}1, n)$ threshold shares and $t < n/2$, providers can multiply two shared values locally and the client interpolates the degree-$2t$ result, so low-degree selection needs neither interaction nor a public-key primitive. That is the route of Obscure [16], whose share multiplications raise the polynomial degree, so that one-round queries need $2l + 1$ servers for a predicate of length l and the adversary must stay below a majority [16, §2.1, §3.2]. A store replicated under one owner's homomorphic key is the direct way to supply the primitive at $t = n - 1$, and it also brings three operational properties that a shared store lacks.

Durability. A sharing with privacy threshold $n-1$ is lost when any one share is lost, whereas a replica set survives the loss of $n - 1$ providers, which is the reason multi-cloud deployments replicate at all. Threshold sharing does not escape the trade-off: a $(t{+}1, n)$ scheme tolerates $n-t-1$ losses, so at $t = n-1$ it degenerates to the (n, n) case.

Graceful degradation. A query needs every provider in the set it is addressed to. With replicas, queries continue over any surviving set of at least two providers, at that set's collusion bound, without touching stored state; a shared store cannot answer until the dealer re-shares.

Key management and churn. Encryption under one owner key lets the owner rotate keys, revoke a provider, or add one by copying ciphertexts. Under sharing, every change to the provider set re-deals the whole store, and the dealer must hold the plaintext to do it.

5.3. Oblivious homomorphic aggregation

Suppose the providers hold additive shares $v_1, \ldots, v_n \in \mathbb{Z}_p^M$ of a vector v and replicas of an encrypted column $\mathrm{C} = (\mathsf{Enc}_{pk}(c_1), \ldots, \mathsf{Enc}_{pk}(c_M))$. Provider j returns

$$\mathrm{ct}_j \;=\; \boxplus_{i \in [M]} v_j[i] \boxdot \mathrm{C}_i,$$

and the DU computes $\boxplus_j \mathrm{ct}_j$, which decrypts to $\langle v, c \rangle$, and decrypts once. Nothing that leaves a provider depends on v beyond its own share, and the response is one ciphertext of fixed size whatever the support of v. CR-SHE instantiates this contraction twice. On the fast path (Section 5.5) v is the DPF's unit vector u_{α_w}, its shares are the evaluation vectors e_j, and C is a precomputed aggregate column over the tag domain. On the flexible path (Section 5.10) v is a selection vector over the records that the client forms after a retrieval and deals as fresh shares, and C is the record column. In both cases the matched set is never materialised at a provider.

Lemma 1 (Algebraic compatibility). *If the DPF output group and the HE plaintext ring are the same $\mathbb{Z}_p$, and $\sum_i |w_f[i]\, m_i| < p$ for every admissible template, then for shares $b_1, \ldots, b_n \in \mathbb{Z}_p^{N_d}$ with $\sum_j b_j = \beta \bmod p$,*

$$\mathsf{Dec}_{sk}\Big(\boxplus_{j \in [n]} \; \boxplus_{i \in [N_d]} \; b_j[i] \boxdot CT_i \Big) \;=\; \sum_{i \in [N_d]} \beta[i]\, m_i \pmod p.$$

PROOF. $\boxdot$ and $\boxplus$ are homomorphisms over the same ring $\mathbb{Z}_p$, so summation commutes with decryption and no reduction is lost: share addition and plaintext addition are taken modulo the same modulus. The magnitude bound prevents plaintext overflow. What remains is decryption correctness, which is a noise-budget question rather than a depth question. A plaintext-to-ciphertext product consumes no multiplicative level but scales the noise by up to the norm of the plaintext, here as large as $p \approx 2^{36}$, because DPF shares are uniform in $\mathbb{Z}_p$, and the contraction sums $\lceil N_d/\ell \rceil$ such products before a rotate-and-sum. The parameters must leave room for that growth. We check the worst case, full-magnitude coefficients across several packed chunks, empirically rather than assume it (Section 9.1). □

Lemma 1 is what makes the two primitives compose. Instantiating the DPF over $\mathbb{Z}_{2^k}$ and the homomorphic scheme over an unrelated plaintext modulus, which is the natural default since the two libraries are chosen independently, silently breaks correctness through wraparound, and the failure is data-dependent and therefore easy to miss in testing.

5.4. Masking the index

Retrieval (Section 5.9) reads a row of the membership index through the DPF. Stored in the clear, that index would hand every provider each posting-list length, which the attack of Section 9.11 turns into tag identities. As DORY does for its Bloom-filter bits [13, §4.1], the DO therefore stores it one-time-padded, here with field-element masks so that arithmetic DPF shares can strip them, and packed:

$$I'[x][c] \;=\; \sum_{b<\pi} I[x][\pi c + b]\, 2^b \;+\; P[x][c] \bmod p,$$

with $\pi = 32$ membership bits per word, where row $P[x]$ is the output of $F'_{K'}$ on $(x, \cdot)$ turned into exactly uniform elements of $\mathbb{Z}_p$ by rejection sampling: each 64-bit PRF word is cut to $\lceil \log_2 p \rceil = 37$ bits and kept only if it is below p, which accepts a candidate with probability $p/2^{37} \approx 0.5$. A packed word is below $2^{32} < p$, so the pad still hides it perfectly, and the index occupies $\lceil N_d/32 \rceil$ words per row instead of N_d: a 32-fold saving in storage, in the retrieval pass and in its response. Because p exceeds 2^{36}, the four spare bits double as a sanity check: a word at or above 2^{32} after unmasking can only come from a corrupted share, and a uniformly corrupted word passes with probability 1/16. A retrieval returns shares of $I'[\alpha_w] = \mathrm{pack}(b) + P[\alpha_w]$, and the DU, which derives $P[\alpha_w]$ from K', subtracts it and unpacks. No provider ever sees an unmasked row or a mask value, and no correction ciphertext is needed.

Theorem 1 (Index hiding). *For any two membership indexes $I_0, I_1 \in \{0,1\}^{N \times N_d}$ packed π bits per word into $\mathbb{Z}_p^{N \times \lceil N_d/\pi \rceil}$, no* PPT *distinguisher tells* $\mathrm{pack}(I_0) + P$ *from* $\mathrm{pack}(I_1) + P$ *with advantage greater than* $\mathbf{Adv}^{\mathrm{prf}}_{F'}$. *In particular the coalition learns no posting-list length, no keyword-frequency multiset, and no membership relation from the stored index.*

PROOF. Replace F' by a truly random function at the cost of $\mathbf{Adv}^{\mathrm{prf}}$. A candidate is then uniform on $\{0, \ldots, 2^{37}-1\}$, and conditioning on acceptance makes each mask value exactly uniform on $\mathbb{Z}_p$, independently of every other. $\mathrm{pack}(I_b) + P$ is then a one-time pad of $\mathrm{pack}(I_b)$ and is uniform on $\mathbb{Z}_p^{N \times \lceil N_d/\pi \rceil}$ for either b. □

Reducing uniform 64-bit words modulo p instead, as is common, biases each mask word: with $r = 2^{64} \bmod p$ its statistical distance from uniform is $r(p-r)/(p\,2^{64}) \approx 8.27 \times 10^{-10}$ for our modulus. Over the $N\lceil N_d/32 \rceil = 146{,}625{,}960$ words of the packed telemetry index the union bound is about 0.12, and over the NN_d words of an unpacked index it exceeds 1 and says nothing. These are upper bounds, not measured distinguishing advantages, but they make rejection sampling, at about two PRF words per mask value, necessary for Theorem 1 to hold as stated.

Remark 1 (Stripping the mask first). An alternative contracts the masked shares b_j directly against the record column and cancels the resulting term $u_f(\alpha_w) = \sum_i w_f[i]\, P[\alpha_w][i]\, m_i$ with an encrypted correction column $U_f = (\mathsf{Enc}_{pk}(u_f(x)))_{x \in [N]}$, retrieved by the same DPF. An earlier version of our design did this. It has two defects. U_f must be precomputed by the DO for each weight vector, so it serves only registered weights, for which the fast path is cheaper; it cannot serve the ad-hoc weights and conjunctions it was meant for. And the correction must itself be encrypted: published in the clear, the count correction $g(x) = \sum_i P[x][i]$ gives $\sum_i I'[x][i] - g(x) = |I[x]|$, the row Hamming weight, restoring the volume leakage the mask removes. The flexible path avoids both by stripping the mask at the client before any contraction.

5.5. Precomputed columns: the single-keyword fast path

The contraction of Section 5.3 costs $\Theta(NN_d)$ ring operations per provider per query, which is the price of hiding the access pattern without preprocessing, by the lower bounds underlying ORAM and PIR [29, 48]. For the common case, an aggregate over the whole posting list of a single keyword under a template registered at setup, this cost is avoidable. The DO precomputes, for every $x \in [N]$,

$$A_f[x] \;=\; \sum_{i \in [N_d]} I[x][i]\, w_f[i]\, m_i \bmod p,$$

and publishes it as $\lceil N/\ell \rceil$ packed ciphertexts. A query then reduces to an oblivious retrieval of one element of an encrypted length-N array:

$$\mathrm{ct}_j \;=\; \boxplus_{x \in [N]} e_j[x] \boxdot A_f[x],$$

costing $O(N)$ pseudorandom-generator calls for the full-domain evaluation plus $O(N/\ell)$ packed ciphertext-plaintext multiplications and $O(\log \ell)$ rotations, *independent of* N_d. No mask correction is needed on this path, because A_f is derived from the unmasked I held by the DO and is itself encrypted.

The fast path supports the templates registered at setup, namely count, sum, per-sensor-band sums, and fixed plaintext-weighted inner products, applied to a single keyword. Conjunctive queries and ad-hoc weight vectors chosen at query time use the flexible path of Section 5.10. Insertion is cheap: a new record carrying τ tags updates A_f at τ addresses in plaintext at the DO, followed by re-encryption of all of the column's packed ciphertexts, for the reason given in Section 5.11; no decryption is involved.

5.6. Packing the response

The straightforward layout spends two ciphertexts on one scalar: the value and its MAC (Section 5.8), each column packed across all ℓ slots and summed over all of them, so that $\ell - 1$ slots of each response go unused. BFV slots have more structure than that. With ring dimension ℓ they form two rows of $\ell/2$, and the automorphisms behind rotation act within each row [72]. CR-SHE uses that shape directly. The DO packs A_f in row 0 and $\widehat{A}_f$ in row 1, chunked $\ell/2$ tags per ciphertext; the provider multiplies each chunk by its evaluation vector, replicated in both rows, adds the chunks, and rotates and sums within the rows. Slot 0 then carries the value share and slot $\ell/2$ the MAC share, in one ciphertext.

Several templates share that ciphertext. For k templates, k a power of two, each row is cut into k segments of $s = \ell/(2k)$ slots, template r occupying segment r of both rows, with $\lceil N/s \rceil$ chunks. Rotating and summing by $1, 2, \ldots, s/2$ leaves the sum of segment r in its first slot, so slot rs of each row carries template r's value or MAC share. Explicitly, chunk c holds, at offset $z < s$ of segment r,

$$\text{row } 0: \; A_{f_r}[cs+z], \qquad \text{row } 1: \; \begin{cases} A_{f_r}[cs+z] & \text{session check,} \\ \delta_{cs+z}\, A_{f_r}[cs+z] & \text{per-row keys,} \end{cases}$$

zero beyond N, and the provider's plaintext for chunk c repeats its evaluation share $e_j[cs+z]$ in every segment of row 0 and the δ_s-carrying share $\hat{e}_j[cs+z]$ in every segment of row 1. The response is one ciphertext for any $k \le \ell/2$; what grows with k is the number of chunks, $\lceil kN/(\ell/2) \rceil$ plaintext-ciphertext products, while the rotations fall from $\log_2(\ell/2)$ to $\log_2 s$. The worked instance of a MEAN below needs its count and sum in one response; count, sum and sum of squares give a variance in one round.

Finally, the provider drops the response to a single RNS tower by modulus switching before it sends it. At multiplicative depth one, decryption is unaffected, and the ciphertext halves. Against the two-ciphertext layout, which costs $2\lceil N/\ell \rceil$ products and $2\log_2 \ell$ rotations per template, packing halves the provider's homomorphic work (rotations dominate at these parameters) and quarters the downlink, and for four templates cuts the downlink sixteen-fold (Section 9.6). The natural single-server alternative, one server answering the same query over the same encrypted columns, uses this same layout with an encrypted one-hot query in place of the DPF shares; Section 9.6 measures it.

5.7. Oblivious range aggregation over data cubes

A single tag answers a narrow question: the mean over one minute, one site, or one value band. The questions IoT analysts ask are ranges, such as the mean temperature at one device over an afternoon, or the

number of hours in which a pollutant sat in its top three bands. Composing such a query from single-tag aggregates costs one query per tag in the range and reveals its length, and the flexible path costs a retrieval per tag. CR-SHE answers rectangular ranges in one round, at a cost independent of both the range and the record count.

Data cubes. The DO registers a *data cube*: d ordered tag families $\mathcal{F}_1, \ldots, \mathcal{F}_d$ of sizes $s_1, \ldots, s_d$, for example device, one-minute window and the decile band of one sensor, such that every record i falls in exactly one cell $c(i) \in \prod_k [s_k]$. For each registered template f the cell aggregate is $C_f[c] = \sum_{i:\, c(i)=c} w_f[i]\, m_i$, and the DO stores the d-dimensional prefix sums, the summed-area table

$$T_f[c] \;=\; \sum_{c' \le c} C_f[c'],$$

with $\le$ taken coordinate-wise, flattened row-major into a column of $M = \prod_k s_k$ entries and packed like a fast-path column (Section 5.6). Prefix-sum cubes are a classical OLAP structure; what is new here is answering them obliviously over encrypted replicas.

Queries. For a box $B = \prod_k [lo_k, hi_k]$ and $\sigma \in \{0,1\}^d$, let corner $\kappa_\sigma(B)$ take $lo_k - 1$ on the axes where $\sigma_k = 1$ and hi_k elsewhere. By inclusion–exclusion,

$$\sum_{c \in B} C_f[c] \;=\; \sum_{\sigma \in \{0,1\}^d} (-1)^{|\sigma|}\, T_f[\kappa_\sigma(B)], \tag{1}$$

where a corner with a coordinate equal to -1 lies outside the cube and contributes 0. The DU sends, for every σ, one DPF key per provider for the point function at $\kappa_\sigma(B)$ with output $\beta_\sigma = (-1)^{|\sigma|} \bmod p$. For a corner outside the cube it sends a *dummy* key, with $\beta_\sigma = 0$ at a uniformly random point. DPF keys hide β as well as the point, so every query to a cube carries exactly 2^d indistinguishable keys per provider, and a provider cannot tell a range that starts at the cube's edge from one in its interior.

Answering. Provider j evaluates its 2^d keys over the full domain of M cells, adds them, $e_j = \sum_\sigma e_{\sigma,j}$, and contracts once against the encrypted table; the response is one ciphertext. The DU adds the n responses and decrypts, and slot 0 holds the range aggregate. In the *verified* layout, row 1 of the table is a copy of row 0 and the query carries a second set of 2^d keys with outputs $\delta_s \beta_\sigma$; the provider places $\hat{e}_j = \sum_\sigma \hat{e}_{\sigma,j}$ in row 1 of the same plaintexts, so slot $\ell/2$ holds δ_s times the aggregate (Section 5.8). An earlier *per-corner* layout instead gave each corner its own slot segment, checked against a per-cell MAC key; it stores the table 2^d times and misses deviations at the queried corner, and we keep it only as a measured baseline.

Cost. Per provider: 2^d full-domain DPF evaluations over M cells (2^{d+1} in the verified layout), $\lceil kM/(\ell/2) \rceil$ plaintext-ciphertext products for $k = |\{f\}|$ templates, and $\log_2(\ell/2k)$ rotations. Uplink is 2^d two-party keys of $O(\lambda \log M)$ bits each, or 2^{d+1} verified. Nothing depends on the box or on N_d.

Magnitude and updates. Every table entry is at most the cube's total, so Lemma 1 requires $\sum_i w_f[i] m_i < p$ over the whole corpus, a stronger condition than for a single tag. With time as the outermost axis and no later slices yet, a batch of records appended to the newest time slice changes T_f only in that slice, so the DO would re-encrypt only the ciphertexts covering it, and since time advances publicly the write pattern would reveal nothing new. When whole-cube replacement is used instead, the update leakage matches that of the fast-path columns in Section 5.11. We have not implemented or measured either update, and their write patterns belong in an update-leakage analysis we have not done. Role-scoped tables (Section 5.9) multiply storage by the number of roles.

Why prefix sums rather than interval FSS. Boyle, Gilboa and Ishai give FSS for d-dimensional intervals with key size $O(\lambda n^d)$, built by the same inclusion–exclusion over 2^d zero-anchored intervals, each shared as a decision tree [20, §3.3, Cor. 3.4]. Evaluating such keys requires the servers to hold each record's coordinates, as Splinter's providers hold public data [12]; over owner-encrypted records the coordinates themselves (which device, which minute, which band) are the sensitive part. Moving the prefix sums into a dense, encrypted table over all M cells keeps the coordinates hidden, reveals only the cube's dimensions, and lets each of the 2^d pieces be a point function with a key of $O(\lambda \log M)$ bits. The price is that cubes and templates must be registered and precomputed, and that cost grows with M rather than with the number of records.

5.8. Tamper evidence

Every response carries a second slot row (Section 5.6), so a check value travels with the answer at no extra downlink. Three ways to fill that row differ in what they catch.

One owner key. Row 1 holds δm_i, or $\delta A_f[x]$, under a single secret δ, and the DU accepts only if $\hat{y} = \delta y$. A provider that adds a constant, corrupts one half, or returns a stale or foreign ciphertext is caught except with probability $1/p$. One that applies the *same* linear substitution to both halves passes: contracting against any e'_j instead of e_j, for instance $k\,e_j$, shifts y and $\hat{y}$ by amounts in the ratio δ, so the tag still verifies.

Per-position keys. Row 1 holds $\delta_x A_f[x]$ with $\delta_x = F''_{K''}(x)$, or $\delta_c T_f[c]$ per cube cell, and the DU checks against the key of the queried position. A substitution $e_j + d$ then passes only if $\sum_{x \neq \alpha_w} d[x](\delta_x - \delta_{\alpha_w}) A_f[x] = 0$, a non-zero linear form in independent keys whenever d touches a non-empty position other than α_w. What survives is a deviation concentrated on the queried position itself, which rescales the answer; a provider that guesses or knows that position wins. Per-position keys also do not exist for the flexible path, whose contraction runs over records.

A per-query secret. The session layout stores no key at all: row 1 of every column, aggregate column or table is a copy of row 0. With each query the DU draws a fresh δ_s uniformly from $\mathbb{Z}_p^*$ and sends a second set of keys for the same points with outputs multiplied by δ_s: f_{α_w, δ_s} on the fast path, $\delta_s \beta_\sigma$ at each corner of a range, and fresh shares of $\delta_s v$ in a flexible round. Each provider places the second evaluation vector in row 1 of the same plaintexts, so the homomorphic work is unchanged and slot $\ell/2$ decrypts to $\delta_s y$. The DU accepts only if $\hat{y} = \delta_s y$.

Theorem 2 (Tamper evidence). *Consider one query in the session layout on any path. Let a coalition C of at most $n-1$ providers return arbitrary responses computed from its members' views, with at least one honest provider, an honest DU that keeps δ_s secret, and no provider colluding with the DU; the coalition does not see the honest providers' keys, and the DU decrypts whatever ciphertexts it receives. Let y be the honest answer. The DU accepts an output $y' \neq y$ with probability at most*

$$\frac{1}{p-1} + \varepsilon,$$

where $\varepsilon = \kappa\,\mathbf{Adv}^{\mathrm{dpf}}$ for a query whose δ_s-carrying set has κ DPF keys per provider ($\kappa = 1$ on the fast path and for a retrieval, 2^d for a range) and $\varepsilon = \mathbf{Adv}^{\mathrm{prf}}$ for a flexible round. Over Q queries the bounds add, whether or not the coalition learns which queries were accepted.

Proof. Let V be the coalition's view: both key sets of its members, the stored ciphertexts, the public and evaluation keys, and everything it saw in earlier queries. Its responses decrypt, summed over C, to (r_0, r_1) in the slots of one template, a function of V, the database and the coalition's coins; the decryption key is independent of δ_s. Let y_C and $\hat{y}_C$ be what the members of C would have contributed honestly, also functions of V and the database. The honest providers contribute $y - y_C$ and $\delta_s y - \hat{y}_C$, so the DU decrypts $y' = y - y_C + r_0$ and $\hat{y}' = \delta_s y - \hat{y}_C + r_1$ and accepts if and only if

$$r_1 - \hat{y}_C = \delta_s\,(y' - y).$$

Replace the coalition's δ_s-carrying keys by keys for the same points and an independent scalar δ'_s. A reduction that knows the points, the signs, the database and δ_s can evaluate the event $\{y' \neq y \wedge r_1 - \hat{y}_C = \delta_s(y' - y)\}$ from the coalition's keys and outputs, so by $(n-1)$-privacy, which hides the output β as well as the point, its probability changes by at most $\kappa\,\mathbf{Adv}^{\mathrm{dpf}}$; for a flexible round the coalition's shares of $\delta_s v$ are uniform, or pseudorandom when a seed is missing, at cost $\mathbf{Adv}^{\mathrm{prf}}$. After the change V is independent of δ_s. Conditioned on V, the database and the coins, everything in the displayed equation except δ_s is fixed, and since $y' - y \neq 0$ at most one of the $p-1$ equally likely values of δ_s satisfies it. Each query uses a fresh δ_s, so feedback from earlier queries concerns independent scalars, and a union bound over the Q queries completes the proof. □

The bound needs no restriction on how a provider deviates: it may substitute vectors, rescale the queried point, swap or mix slot rows, replay an old response or return any ciphertext at all. It does not guarantee output delivery, since a deviating provider can always force an abort. It also leaves one channel open: whether the DU aborts can depend on the data, for example on whether a cell a provider chose to perturb is empty,

so a DU that reveals its aborts can leak up to one bit about the data per query to a malicious provider, though nothing about the query, whose keys are pseudorandom to it. A DU that retries silently through another provider set closes that channel. The 200 injected trials per deviation in Section 9.14 are empirical checks of the implementation, not a measurement of the $1/(p-1)$ bound. Against per-position keys the cost is a second key set and a second full-domain evaluation per provider, with no extra homomorphic product and no stored key; Section 9.14 measures all three modes on every path.

5.9. Record retrieval and role-scoped access

When the DU needs payloads, providers return b_j directly; the DU subtracts $P[\alpha_w]$, unpacks b, and fetches the payloads with a batch of $k_{\max}$ DPF retrievals padded to a public bound, as in Splinter [12]. The response is $\lceil N_d/32 \rceil$ words whatever $|S|$.

Why providers cannot check a query. DPF privacy hides the queried row, so no provider can check *which* keyword, cell or range a query targets. Keys that are not point functions (an n-party key *is* a share vector, and a two-party key is pseudorandom) give arbitrary linear combinations of rows, columns or cells, and the flexible path's second round is by construction an oracle for any linear function of the record column. A user with query access can therefore read everything its columns and mask key cover. Proofs carried with the key [24, 37] or verifiable DPFs [25] restrict which keys are accepted, at the price of a short server-to-server exchange in the constructions we know [23]. We restrict instead what the columns and keys cover.

Role-scoped columns and keys. The DO assigns every record a role $\rho(i) \in [R]$, for example the agency that owns the device, and lays out record identifiers so that each packed word of the index holds records of one role, padding with empty records where a role's records end. It derives one mask key per role, $K'_\rho = F_{K'}(\rho)$, and draws word c of every index row from $K'_{\rho(c)}$; a user of role ρ receives K'_ρ only. For every role the DO also builds the aggregate columns A^ρ_f, the cube tables T^ρ_f and the record column from that role's records alone, zero elsewhere. A provider answers a role-ρ user from role ρ's columns, selected by the user's authenticated identity; that policy lookup is the only role-dependent provider logic, and it needs no exchange with other providers.

Proposition 2 (Role confinement). *Suppose every provider authenticates the data user's role and applies that role's columns on every response path, and no provider colludes with the data user. Then for any sequence of queries a role-ρ user sends, including malformed keys and arbitrary share vectors, its view is simulatable from the role-ρ records and the public dimensions, up to* $\mathbf{Adv}^{\mathrm{prf}}$.

Proof. Fast-path, range and flexible responses are linear functions of the role-ρ columns, which are functions of role-ρ records only. A retrieval returns linear combinations of masked index entries. Entries in role-ρ words depend on role-ρ records and on masks the user can derive. Entries in other words carry masks from keys $K'_{\rho'}$, $\rho' \neq \rho$, which the user lacks; replacing F by a random function at cost $\mathbf{Adv}^{\mathrm{prf}}$ makes those masks one-time pads, so the entries are uniform whatever the records. □

The mechanism costs storage, not interaction: columns, tables and record columns are replicated per role, while the large masked index is shared. It reveals each query's role to the providers and each role's size, rounded up to a word, in the public layout. Confinement is conditional on provider-side enforcement: a provider that colludes with an unauthorised user defeats it. It does not express policies finer than a record partition, such as per-tag rights within a role; revoking a user of a role means re-keying that role and re-masking its words; and a streaming deployment must keep one hot buffer per role, so that every packed word stays within one role.

5.10. The flexible path: conjunctions and ad-hoc weights

Registered single-keyword templates cover the common case. For anything else, such as a conjunction or disjunction of keywords, a weight vector chosen at query time, or a threshold on the matched set, the DU runs two rounds.

Round one is a retrieval (Section 5.9) for each keyword involved, after which the DU holds the posting lists and forms whatever selection vector it needs over the records, for example $v = w \circ (b_{w_1} \wedge b_{w_2})$ for an ad-hoc weight vector w and a conjunction of two keywords.

Round two deals v as fresh additive shares $v = \sum_j v_j$ over $\mathbb{Z}_p$, compressed exactly like the n-party key of Section 3: $n-1$ providers receive a λ-bit seed whose PRF expansion is their share, and one receives the explicit difference vector. Each provider runs the contraction of Section 5.3 against the record column, packed with m_i in row 0 and m_i (session check, with shares of $\delta_s v$ in row 1) or δm_i (stored key) in row 1 of $\lceil N_d/(\ell/2) \rceil$ ciphertexts, and returns one ciphertext. The DU adds the n responses, decrypts once and checks $\hat{y} = \delta_s y$ (session) or δy (stored key). The magnitude bound of Lemma 1 is the DU's to check, against a public bound on m_i, since it alone knows v.

Round two costs $\lceil N_d/(\ell/2) \rceil$ plaintext-ciphertext products and $\log_2(\ell/2)$ rotations per provider, λ bits of uplink to $n-1$ providers and $N_d \lceil \log p \rceil$ bits to one, and one ciphertext down. Every share a coalition of $n-1$ providers holds is uniform, or pseudorandom for the seeds, independently of v, so round two adds to the coalition's view nothing that depends on the query (Theorem 4). The DU learns S and $|S|$, which $\mathcal{L}^{\mathrm{DU}}$ already contains.

A single round is not possible here in general: a conjunction is the product of two selection vectors, which no linear contraction of shares computes, and an ad-hoc weight vector would need a mask correction the DO cannot precompute (Remark 1).

5.11. Dynamic ingest

IoT streams are append-only. CR-SHE keeps a static tier and a hot buffer of at most B records scanned by the same contraction, folded into a rebuilt tier every B insertions. Because the coalition's per-query view is independent of the query (Theorem 4), a query reveals nothing about records inserted before or after it, which is forward and backward privacy in the usual sense; what updates themselves expose is the public tier metadata in the setup leakage, and we do not analyse update leakage beyond that. Three rules keep updates from leaking. *Rows never move*: a new keyword takes the next free, masked, all-zero row of D, so only exhausting the provisioned headroom is visible. *A fresh mask key per static tier*: a rebuild re-lays the record axis, and reusing K' would expose the change in membership. *Whole columns are replaced*: re-encrypting only the affected ciphertexts of A_f would reveal which blocks of tags changed; summed-area tables with time as the outermost axis would be the exception (Section 5.7), since only the newest, publicly known slice changes. The C++ prototype implements and measures the hot buffer and the fast-path rebuild (Section 9.12); the reference implementation does not, and neither implements the summed-area-table update.

5.12. Worked instance

A clinician queries the tag `arrhythmia` with the registered template MEAN. The DU derives α_w and sends one DPF key per provider. Each provider performs a full-domain pass, contracts against the SUM and COUNT columns packed side by side, and returns one ciphertext carrying both values and both MACs. The DU adds the shares, decrypts once, verifies the MACs, and divides. No provider, and no coalition of up to $n-1$, learns the tag queried, which records contributed, how many did, or the mean itself.

6. Security analysis

Leakage profile. We define $\mathcal{L} = (\mathcal{L}_{\mathrm{Setup}}, \mathcal{L}^{\mathrm{CP}}, \mathcal{L}^{\mathrm{DU}})$ with an observer split:

$$\begin{aligned} \mathcal{L}_{\mathrm{Setup}}(DB) &= (n, t, N, N_d, p, \ell, \mathrm{layoutMeta}, \mathrm{cubeMeta}, \mathrm{roleMeta}, \mathrm{tierMeta}), \\ \mathcal{L}^{\mathrm{CP}}_{\mathrm{Query}} &= \mathrm{class}(q), \\ \mathcal{L}^{\mathrm{DU}}_{\mathrm{Query}} &= \big(|S|,\ f(\mathrm{records}(S))\big). \end{aligned}$$

The setup leakage is everything a provider can see in its replica: layoutMeta gives the registered templates and the segment and ciphertext-column shapes, cubeMeta the registered cubes and their dimensions $(s_1, \ldots, s_d)$, roleMeta the number of roles and each role's span of packed words, and tierMeta the tier sizes and epochs. Here $\mathrm{class}(q)$ says whether a query is a fast-path aggregate over a named layout of registered templates, a range aggregate over a named cube and layout, a retrieval, or the second round of a flexible query, together with the querying user's role and whether the query carries the verification key set. The coalition learns that and the public dimensions of the deployment, and nothing else: not the keyword, not the range or whether it touches the cube's edge, not the access pattern, not $|S|$, not the weights, not the result. In contrast to a

Algorithm 1 Outsourcing at the data owner.

procedure $\mathsf{Setup}(1^\lambda, n, t, p)$
  $D \leftarrow \emptyset$; $K', K'' \leftarrow \{0,1\}^\lambda$; $\delta \leftarrow \mathbb{Z}_p^*$
  $(pk, sk) \leftarrow \mathsf{KGen}(1^\lambda, L_{\mathrm{HE}}, p, \ell)$
  $pp \leftarrow (n, t, N, N_d, p, \ell, \{w_f\})$
  return $(D, K', \delta, pk, sk, pp)$
end procedure

procedure $\mathsf{BuildIndex}(D, K', DB)$
  $D(w) \leftarrow |D|$ for each new w ▷ rows never move
  $I[D(w)][i] \leftarrow 1$ for each keyword w of record i
  $P[x] \leftarrow$ rejection-sampled $F'_{K'}(x, \cdot)$
    uniform on $\mathbb{Z}_p^{\lceil N_d/\pi \rceil}$, for all $x \in [N]$
  $I' \leftarrow \mathrm{pack}(I) + P \bmod p$
  return I' ▷ replicated to all CP_j
end procedure

procedure $\mathsf{Precompute}(pk, K', DB, \{w_f\})$
  for all registered templates f **do**
    $A_f[x] \leftarrow \sum_i I[x][i]\, w_f[i]\, m_i$
    $\widehat{A}_f[x] \leftarrow \delta_x A_f[x]$, $\delta_x \leftarrow F''_{K''}(x)$
    pack A_f in row 0, $\widehat{A}_f$ in row 1,
      templates in segments (§5.6); encrypt
  end for
end procedure

procedure $\mathsf{EncData}(pk, DB)$
  pack m_i in row 0, δm_i in row 1; encrypt
    $\lceil N_d/(\ell/2) \rceil$ ciphertexts
  symmetric-encrypt opaque payloads
end procedure

design in which the matched set is returned to the providers for evaluation, and in contrast to an unmasked index, $\mathcal{L}_{\mathrm{Setup}}$ here contains no posting-list lengths and no membership structure, by Theorem 1. Retrieval adds the public padding bound $k_{\max}$ to $\mathcal{L}^{\mathrm{CP}}$. A conjunctive query is two retrievals and one flexible round, adding only result sizes to $\mathcal{L}^{\mathrm{DU}}$, never to the coalition.

Definition 1 ($\mathcal{L}$-security against t-collusion). In $\mathbf{Real}_{\mathcal{A},\Pi}(1^\lambda)$: (1) $\mathcal{A}$ outputs (DB, C) with $|C| \le t$; (2) the challenger runs Setup, $\mathsf{BuildIndex}$, $\mathsf{Precompute}$, $\mathsf{EncData}$ and gives $\mathcal{A}$ the static view $(I', \mathrm{CT}, \widehat{\mathrm{CT}}, \{A_f, \widehat{A}_f\}_f, \{T_f, \widehat{T}_f\}_{f,\mathrm{cube}}, pk, pp)$; (3) for $q = 1, \ldots, Q$, $\mathcal{A}$ adaptively issues a query (a keyword with a template layout, a box of a registered cube with a layout, a keyword to retrieve, or a selection vector v_q for a flexible round) and receives the coalition's per-query view: its DPF keys $\{\kappa_{q,j}\}_{j \in C}$ or its shares $\{v_{q,j}\}_{j \in C}$, including the δ_s-carrying set of a verified query, and the responses those providers compute; (4) $\mathcal{A}$ outputs a bit. In $\mathbf{Ideal}_{\mathcal{A},\mathcal{S},\mathcal{L}}(1^\lambda)$ a PPT simulator $\mathcal{S}$ produces the views given only $\mathcal{L}_{\mathrm{Setup}}$ and the per-query leakage. Π is $\mathcal{L}$-adaptively-secure against t-collusion if for every PPT $\mathcal{A}$ corrupting $\le t$ providers there is a PPT $\mathcal{S}$ with $|\Pr[\mathbf{Real} = 1] - \Pr[\mathbf{Ideal} = 1]| \le \mathsf{negl}(\lambda)$.

Theorem 3 (Correctness). *Fix a database DB, a keyword w, and a registered template f satisfying the magnitude bound of Lemma 1. Then* $\mathsf{CombineDec}$ *returns $y = \sum_{i \in S} w_f[i]\, m_i$ with $S = \{i : I[\alpha_w][i] = 1\}$ on the fast path, a range query on a box B of a registered cube whose total is below p returns $\sum_{i:\, c(i) \in B} w_f[i]\, m_i$,* $\mathsf{Retrieve}$ *returns exactly S, and a flexible round on a selection vector v satisfying the magnitude bound returns $\sum_i v[i]\, m_i$, except with the negligible probability that leveled-HE decryption fails.*

Proof. By DPF correctness $\sum_j e_j[x] = 1$ at $x = \alpha_w$ and 0 elsewhere.

Fast path. $\boxplus_j \mathrm{ct}_j$ decrypts, by Lemma 1 applied with $\beta = \left(\sum_j e_j\right)$ over the array A_f, to $A_f[\alpha_w] = \sum_i I[\alpha_w][i] w_f[i] m_i = \sum_{i \in S} w_f[i] m_i$.

Range. The 2^d keys of a range query share the point functions $\beta_\sigma\, u_{\kappa_\sigma}$, with $\beta_\sigma = 0$ for a corner outside the cube. In the combined layout $\sum_j e_j = \sum_\sigma \beta_\sigma u_{\kappa_\sigma}$, so by Lemma 1 applied over the column T_f the

Algorithm 2 Query, at the data user and at provider CP_j.

procedure $\mathsf{Token}(D, w, f)$ ▷ at the DU
  $\alpha_w \leftarrow D(w)$
  $(\kappa_1, \ldots, \kappa_n) \leftarrow \mathsf{Gen}(1^\lambda, \alpha_w, 1)$ over $\mathbb{Z}_p$
  verified: $\delta_s \leftarrow \mathbb{Z}_p^*$; $(\hat{\kappa}_1, \ldots, \hat{\kappa}_n) \leftarrow \mathsf{Gen}(1^\lambda, \alpha_w, \delta_s)$
  return $(\kappa_j, \hat{\kappa}_j, f) \rightarrow \mathrm{CP}_j$
end procedure

procedure $\mathsf{FastAgg}(\kappa_j, \hat{\kappa}_j, f, A_f, \widehat{A}_f)$ ▷ single keyword (Algorithm 1 columns)
  check the shape of $\kappa_j, \hat{\kappa}_j$ ▷ §5.9
  $e_j[x] \leftarrow \mathsf{Eval}(j, \kappa_j, x)$; $\hat{e}_j[x] \leftarrow \mathsf{Eval}(j, \hat{\kappa}_j, x)$, $x \in [N]$ ▷ $O(N)$ PRG
  $\mathrm{ct}_j \leftarrow \boxplus_c E_{j,c} \boxdot \mathrm{A}_c$ ▷ $O(N/\ell)$ HE
    $E_{j,c}$: chunk c of e_j in row 0, $\hat{e}_j$ (or e_j) in row 1
  rotate and sum within segments; compress
  return ct_j ▷ one ct, value + MAC
end procedure

procedure $\mathsf{Deal}(v, \delta_s)$ ▷ at the DU, flexible
  $v = \sum_j v_j$, $\delta_s v = \sum_j \hat{v}_j$: seeds to $n-1$ providers,
    explicit difference to one
end procedure

procedure $\mathsf{FlexAgg}(v_j, \hat{v}_j, \mathrm{CT})$ ▷ round two ($V_{j,c}$: v_j in row 0, $\hat{v}_j$ or v_j in row 1)
  $\mathrm{ct}_j \leftarrow \boxplus_c V_{j,c} \boxdot \mathrm{CT}_c$; rotate and sum
  return ct_j
end procedure

procedure $\mathsf{Retrieve}(\kappa_j, I')$
  return $b_j \leftarrow \sum_x e_j[x] \cdot I'[x]$ ▷ fixed size
end procedure

procedure $\mathsf{CombineDec}(sk, K', \delta, \cdot)$ ▷ at the DU
  $(y, \hat{y}) \leftarrow$ slots $(0, \ell/2)$ of $\mathsf{Dec}(sk, \boxplus_j \mathrm{ct}_j)$
  abort if $\hat{y} \neq \delta_s y$ (session), or $\delta_{\alpha_w} y$, δy (stored keys)
  retrieval: $b \leftarrow \mathrm{unpack}\big((\sum_j b_j) - P[\alpha_w]\big)$
    $S \leftarrow \{i : b[i] = 1\}$
  return y, and S if retrieving
end procedure

response decrypts to $\sum_\sigma \beta_\sigma T_f[\kappa_\sigma]$, and in the verified layout row 1 decrypts to δ_s times the same sum; in the per-corner baseline segment σ decrypts to $\beta_\sigma T_f[\kappa_\sigma]$ and the DU adds them. By (1) that sum is the box aggregate modulo p. The true aggregate lies in $[0, p)$ because it is at most the cube's total, so the reduction loses nothing, even though individual signed terms are negative.

Retrieval. $\sum_j b_j = \sum_x \big(\sum_j e_j[x]\big) I'[x] = I'[\alpha_w] = \mathrm{pack}(b) + P[\alpha_w]$, so $\big(\sum_j b_j\big) - P[\alpha_w] = \mathrm{pack}(b)$ exactly, and the DU, which derives $P[\alpha_w]$ from K', unpacks b.

Flexible round. $\sum_j v_j = v$, so by Lemma 1 applied with $\beta = v$ over the record column, $\boxplus_j \mathrm{ct}_j$ decrypts to $\sum_i v[i]\, m_i$ in slot 0 and $\delta \sum_i v[i]\, m_i$ in slot $\ell/2$.

Packing. Rotations act within slot rows and the rotate-and-sum covers one segment, so the slot that carries template r receives only the products of template r's segment, and the value and MAC rows do not mix.

The dictionary is injective by construction, so row α_w is exactly the records containing w. Decryption correctness under the noise growth discussed in the proof of Lemma 1 contributes the negligible failure term. The check of Section 5.8 passes with certainty for honest providers: in the session layout row 1 holds the same data and the second key set shares δ_s times the same point functions or vector, so by the same argument slot $\ell/2$ decrypts to $\delta_s y$; with stored keys, δ or δ_{α_w} distributes over the linear contraction, $\sum_x e[x]\, \delta_x A_f[x] = \delta_{\alpha_w} A_f[\alpha_w]$ when $e = u_{\alpha_w}$. □

Theorem 4 (t-collusion leakage security). *If F and F' are secure PRFs, $(\mathsf{Gen}, \mathsf{Eval})$ is an $(n-1)$-private DPF, and the homomorphic and symmetric schemes are IND-CPA, then CR-SHE is $\mathcal{L}$-adaptively-secure against t-collusion in the sense of Definition 1, for $t = n-1$ and $\mathcal{L}^{CP}_{\mathrm{Query}} = \mathrm{class}(q)$. Concretely, for*

every PPT $\mathcal{A}$ *there exist* PPT $\mathcal{S}$ *and* $B_1, \ldots, B_4$ *with*

$$\big|\Pr[\mathbf{Real}{=}1] - \Pr[\mathbf{Ideal}{=}1]\big| \le \mathbf{Adv}^{\mathrm{prf}}_{F',B_1} + Q \cdot \big(2^{d_{\max}+1}\mathbf{Adv}^{\mathrm{dpf}}_{B_2} + 2\,\mathbf{Adv}^{\mathrm{prf}}_{B_4}\big) + m \cdot \mathbf{Adv}^{\mathrm{cpa}}_{B_3},$$

where m is the number of ciphertexts in the coalition view. As is standard for BFV, IND-CPA is assumed to hold even given the relinearisation and rotation keys the providers need (circular security). The theorem is stated for one static tier; with a fresh K' per tier (Section 5.11) it applies to each tier independently, with one PRF term per tier.

Proof. Take $|C| = n-1$ without loss of generality; a smaller coalition holds a subset of the same state. Let $H_0 = \mathbf{Real}$.

H_1 *(PRF to random, index to zero).* Replace F' by a truly random function, at cost $\mathbf{Adv}^{\mathrm{prf}}_{F',B_1}$. The mask is then an exactly uniform one-time pad (Theorem 1), so building I' from the all-zero index instead of I changes nothing; I' now depends only on (N, N_d).

H_2 *(DPF keys to simulated).* Replace every DPF key the coalition holds by $\mathcal{S}_{\mathrm{DPF}}(1^\lambda, C, \cdot)$ for its domain, licensed by $(n{-}1)$-privacy, which hides the output β as well as the point. A range query to a d-dimensional cube carries 2^d independent keys, dummy keys included, and 2^d more when it is verified, so a hybrid over all keys costs $Q\,2^{d_{\max}+1}\mathbf{Adv}^{\mathrm{dpf}}_{B_2}$, where $d_{\max}$ is the largest registered cube dimension. In particular the simulated keys no longer depend on δ_s. The per-query key material now depends only on C, the domain and the query class; in particular it no longer depends on which corners were dummies.

H_2' *(flexible shares to uniform).* In each flexible round at least one share lies outside C. If it is the explicit difference vector, the coalition's shares are seed expansions independent of v_q. If it is a seed's expansion, the explicit vector is v_q (and $\delta_s v_q$ in the verified layout) minus a PRF output the coalition cannot compute, and replacing both outputs by uniform vectors costs $2\,\mathbf{Adv}^{\mathrm{prf}}_{B_4}$. Either way the coalition's shares become uniform and independent of (v_q, δ_s), over at most Q rounds.

H_3 *(ciphertexts to encryptions of* 0*).* Replace each of the m ciphertexts in the coalition view, namely the record column, the columns $A_f, \widehat{A}_f$ and the tables $T_f, \widehat{T}_f$, by encryptions of 0 under pk, at cost $m \cdot \mathbf{Adv}^{\mathrm{cpa}}_{B_3}$, since the coalition holds only pk.

Simulator. The responses $\mathrm{ct}_{q,j}$ need not be simulated separately: each is a deterministic function of $\kappa_{q,j}$ or $v_{q,j}$, the query class, and the provider's stored state, all of which $\mathcal{S}$ possesses in H_3. Compression is a public, deterministic map and changes nothing. $\mathcal{S}$ therefore regenerates the entire coalition view from $\mathcal{L}_{\mathrm{Setup}}$ and class(q) alone, so $\mathbf{Ideal}_{\mathcal{A},\mathcal{S},\mathcal{L}}$ matches H_3; summing the terms proves the theorem. □

Remark 2 (Rounds and leakage). Suppose the client recovers S and then requests $\mathsf{Compute}(pk, \{\mathrm{CT}_i\}_{i\in S}, f)$ from the providers. The coalition's per-query view then contains S itself, which is a function of the queried keyword and the database. No simulator given only data-independent leakage can produce it, so an empty per-query leakage profile is *unattainable* in that design rather than merely loose. The flexible path has the same two rounds, but its second round sends fresh shares of the selection instead of the selection, and H_2' shows those are simulatable. What makes Theorem 4 true is contracting a share at the provider, not the number of rounds.

Remark 3 (Confidentiality and degradation). For two databases of equal public dimensions differing only in contents, Theorem 4 makes each coalition view indistinguishable from a distribution depending only on $\mathcal{L}_{\mathrm{Setup}}$, which is identical for both; the executions differ by at most $m \cdot \mathbf{Adv}^{\mathrm{cpa}}$, with the content dependence isolated in H_3. The same proof applies for any $|C| \le n-1$, since $(n{-}1)$-privacy holds for every strict subset; a coalition of all n providers is outside the model, and against it the guarantee degrades to IND-CPA confidentiality of the records with the index still masked under F'.

Remark 4 (Beyond semi-honest). Theorem 4 is proved for semi-honest providers. Because providers never interact and receive nothing but keys or shares, a coalition that deviates sees the same view, so its deviation buys it no information about the query, and Theorem 2 makes any deviation that changes an answer evident to the DU. Two things are not covered: output delivery, since a deviating provider can force an abort, and the abort events themselves, which can carry up to one bit about the data per query if the DU reveals them (Section 5.8). This is why Table 1 records *abort* rather than full malicious security.

7. Complexity analysis

Table 3 summarises the asymptotic costs. Four entries deserve comment because they correct the intuitive accounting.

First, the selection contraction of a retrieval, and hence of the flexible path's first round, is $\Theta(NN_d/\pi)$ ring operations ($\pi = 32$ packed bits per word, $\Theta(NN_d)$ unpacked), not $\Theta(N)$: a full-domain evaluation produces N share values, each of which multiplies an index *row* of $\lceil N_d/\pi \rceil$ packed words. Counting only the $O(N)$ pseudorandom-generator calls of the evaluation omits the dominant term. With a small modulus and vectorised arithmetic these are cheap word operations, and the pass is embarrassingly parallel, but the asymptotic is what it is: this is the ORAM and PIR lower-bound price for hiding the access pattern from a coalition without preprocessing [29, 48]; preprocessing PIR avoids it at the cost of client hints that updates invalidate [40].

Second, the fast path of Section 5.5 removes the N_d factor entirely, at $O(N)$ generator calls plus $O(N/\ell)$ packed ciphertext operations, at the cost of restricting queries to single keywords and templates registered at setup.

Third, the aggregate response is one ciphertext, for up to $\ell/2$ templates, and, crucially, *independent of* $|S|$. A response whose size grew with the result set would leak the result-set size to the coalition and contradict $\mathcal{L}^{\mathrm{CP}}$. Retrieval responses are $\lceil N_d/32 \rceil$ words of fixed size for the same reason. Range queries likewise return one ciphertext, for any box.

Fourth, the single-server alternative of Section 5.6 needs no non-collusion assumption but pays in two places. On the fast path its query is $\lceil N/(\ell/2) \rceil$ fresh ciphertexts instead of an $O(\lambda \log N)$ key, and its contraction uses ciphertext-ciphertext products. On retrieval and the flexible path it must multiply an encrypted N-vector by the packed $N \times \lceil N_d/32 \rceil$ index, about $N\lceil N_d/32 \rceil/\ell$ plaintext-ciphertext products with diagonal packing [72], where CR-SHE does $\Theta(NN_d/32)$ word operations. Both are linear in NN_d: the gap is the constant ratio of a homomorphic slot operation to a machine-word operation, which Section 9.6 bounds from below. What does not shrink with better kernels is the client side: a $\lambda \log N$-bit key against $\lceil N/(\ell/2) \rceil$ fresh encryptions.

Table 3
Asymptotic costs. γ is the per-provider DPF key size, $O(\lambda \log N)$ at $n = 2$; ℓ is the SIMD slot count.

Resource	Per provider	Data user
Index storage	$O(NN_d \log p/32)$, packed	n/a
SAT storage, d-cube	$O(kM/\ell)$ per role	n/a
Ciphertext storage	$O(N_d/\ell) + O(N/\ell)$ per f	n/a
Query uplink	$O(\gamma)$	$O(n\gamma)$
Flexible uplink	λ, or $N_d\lceil \log p \rceil$ bits	$O(N_d \log p)$
Aggregate downlink	1 ct	n ct
Retrieval downlink	$\lceil N_d/32 \rceil$ words, fixed	$O(nN_d)$ bits
Fast path	$O(N)$ PRG, $O(N/\ell)$ HE	1 decrypt
Range, d-cube, M cells	$2^{d+1} \cdot O(M)$ PRG, $O(kM/\ell)$ HE	2^{d+1} keygen, 1 decrypt
Range uplink (verified)	$2^{d+1}\gamma$	$n2^{d+1}\gamma$
Retrieval / round one	$O(N)$ PRG, $\Theta(NN_d/32)$ ring	$O(N_d)$
Flexible round two	$O(N_d/\ell)$ HE, $O(\log \ell)$ rot.	1 decrypt
Owner precomputation	postings per f; $O(NN_d)$ mask	n/a
Insertion, τ tags	$O(\tau)$ updates, $O(N/\ell)$ re-enc.	n/a

8. Implementation

Two implementations share the parameters below. A C++17 prototype implements the single-keyword path in the two-ciphertext layout with a single MAC key; it produced the measurements on the real corpora for the fast path and deployment, reported where the measured quantity does not depend on the later layout. An open reference implementation (Python driving OpenFHE's C++ kernels) implements the full construction of Section 5: range aggregation over data cubes in the combined, verified and per-corner layouts, the packed response, all three verification modes on every path, role-scoped columns and mask keys, the

packed and masked index with rejection-sampled masks, retrieval, the flexible path, and baseline (vi). Its 83 tests include DPF checks at every point of every domain up to depth 8, range answers against brute force for $d \leq 3$ and $n \leq 3$, and failure controls that must and do fail: a flipped corner sign and an out-of-cube corner treated as real produce wrong answers; a provider told δ_s passes the session check with a wrong answer; the single-key MAC accepts a scaled share; an index masked under one key unmasks every word; and the additive bit packing that a draft review flagged carries a repeated record identifier into the next bit. Six deliberate source mutations of the range code and eight of nine mutations of the verification, role and packing code are caught; the ninth is equivalent (with identifiers made unique, adding and or-ing bits coincide).

Primitives. The two-party DPF is the Boyle–Gilboa–Ishai GGM-tree construction [20] with fixed-key AES-128 in the Matyas–Meyer–Oseas form $G(s) = \mathrm{AES}_k(s) \oplus s$ under three fixed keys, evaluated over the full domain in one pass. The homomorphic layer is leveled BFV in OpenFHE [73] (1.2.3 in C++, 1.5.1 in Python) at plaintext modulus $p = 68{,}724{,}326{,}401$, a 37-bit prime with $p \equiv 1 \bmod 2^{17}$, ring dimension 8,192, multiplicative depth 1, at the 128-bit classical security level. In both implementations the DPF output group and the BFV plaintext ring are one modulus object, so the composition error that Lemma 1 warns about cannot be written, and a template or cube whose total would reach p is rejected at setup.

Corpora. The primary corpus is the Environmental Sensor Telemetry dataset of 405,184 MQTT messages from three sensor arrays [74], indexed under the device, a one-minute window, decile bands of five sensor channels and two boolean flags: $N = 11{,}580$ tags over 3,646,656 postings (median 35, mean 314.9, maximum 404,702), aggregating temperature in hundredths of a degree; the largest single-tag aggregate, 908,575,470, leaves 75.6× headroom below p. The second is the UCI Beijing Multi-Site Air-Quality dataset [75, 76]: 420,370 hourly records from twelve sites after dropping 398 with a missing temperature, $N = 35{,}162$ tags over 4,624,070 postings, with 98.3× headroom. Together the two corpora hold 825,554 records and 46,742 tags. The reference implementation's loader rebuilds both; it agrees with the C++ builder on N, N_d and the posting total, which hold for any band rule, and on the primary corpus's maximum posting length and largest single-tag aggregate, but on the second corpus it gives 98,878 and 676,076,034 where the C++ builder gave 102,344 and 698,963,226, so the two assign some band edges differently. Range experiments use cubes built from both corpora and a synthetic cube (Section 9.2).

Baselines. (i) a plaintext scan; (ii) single-server searchable encryption, which leaks search and access patterns and $|S|$; (iii) Path ORAM with $Z = 4$; (iv) a DORY-style [13] search-only baseline, our selection stopped at the selection vector; (v) a faithful homomorphic equality scan, $\mathrm{eq}(a, b) = 1 - (a - b)^{q-1}$, measured on one batch and extrapolated (marked †); and (vi) a single server holding the same encrypted columns, queried with an encrypted one-hot vector, which needs no non-collusion assumption and so isolates what that assumption buys.

Machines. C++ measurements: one AMD EPYC 7J13, 64 cores, 64 GB, Ubuntu 24.04, GCC 13 with OpenMP and AES-NI, medians of 11 runs unless stated. Reference implementation: synthetic-data runs on a cloud VM with four vCPUs of an Intel Xeon at 2.1 GHz with AES-NI and 16 GB; real-corpus runs (correctness, range on real cubes, leakage) on an AMD EPYC 7J13 server with 32 vCPUs and 31 GB, Ubuntu, Python 3.12.3; one OpenMP thread, medians of 5–21 runs. Every JSON output carries its environment stamp, and every table and figure built from them is generated by a script rather than transcribed. Latencies from different machines are not comparable with each other. The C++ fast-path figures use the two-ciphertext layout and so bound the packed layout from above.

9. Results analysis and discussion

9.1. Correctness

Every result below comes from an implementation that first has to compute the right answer (Theorem 3). The C++ prototype matched the plaintext ground truth exactly, with the MAC verifying, for 1,000 random tags per template and $n \in \{2, 3, 4\}$ on both real corpora, returned exactly the posting list on retrieval, and sent a byte-identical response for matched sets of size 0 and 4,999. The reference implementation matches the ground truth for every range query in its benchmarks and tests, and, on a synthetic corpus shaped like the primary one, for 200 random tags at each $n \in \{2, 3, 4\}$ on the fast path, retrieval and the flexible path with ad-hoc weights, with a byte-identical 132,081 B response for the shortest and longest posting lists. On

both real corpora it matched the ground truth for 200 random tags at each $n \in \{2, 3, 4\}$ on all three paths, every one of the 1,800 queries per corpus correct, again with a 132,081 B response throughout, and every range query on the real cubes (Section 9.2) was correct.

9.2. Range aggregation

Setup. The range path is measured in the reference implementation, first on a synthetic cube with the primary corpus's dimensions, 3 devices, 11,523 one-minute windows and 10 value bands of one sensor channel, $M = 345{,}690$ cells over 405,184 records, with templates COUNT and SUM, to compare the three layouts and sweep the cube size (Tables 4 and 5); then on cubes built from the two real corpora (Table 6). Because a summed-area table is encrypted across all M cells regardless of occupancy, the cost depends on the cube's dimensions and the number of templates, not on the records, which the real-cube runs confirm. A query fixes one device, a window of L minutes and bands 3–7, so $d = 3$ and each provider receives 8 keys, or 16 in the verified layout. Every decrypted answer is checked against the plaintext ground truth. One thread, medians of 5 runs, interquartile ranges in the result files.

Table 4
Range aggregation per provider against window length L, $M = 345{,}690$ cells, $d = 3$, two templates. Reference implementation, one thread. Every query returns 132,081 B; the uplink per provider is 2,760 B (8 keys), or 5,520 B (16 keys) when verified.

L (min)	Per-corner	Combined	Verified (session)	
	total (ms)	total (ms)	DPF eval (ms)	total (ms)
1	3290.9	891.7	1055.0	1410.3
60	3436.1	913.7	1152.4	1437.5
240	3240.6	781.5	1143.9	1395.3
1,440	3253.3	810.2	1265.9	1527.2
11,523	3298.1	843.7	1103.4	1471.5

Cost does not depend on the range (Table 4). From a one-minute window to the whole 11,523-minute timeline, a provider spends 0.78–0.91 s in the combined layout, 1.40–1.53 s in the verified layout and 3.24–3.44 s in the per-corner layout. Every query receives one 132,081 B ciphertext. The whole-timeline box already starts at the cube's edge, so four of its eight corners are dummies; a 240-minute box at the cube's origin, on which seven of the eight are dummies, costs the same (937.8 ms combined, 1,385.0 ms verified) and sends the same number of keys. The data user spends 6–19 ms generating keys and 1.1–1.9 ms combining, checking and decrypting.

What verification costs. The verified layout stores the same 169 ciphertexts as the combined layout, with a copy of the table in place of a MAC row, and performs the same homomorphic products; what it adds is the second set of eight keys, 2,760 B more uplink, and their full-domain evaluation. Evaluating both key sets takes 1.06–1.27 s of its total, against 0.45–0.51 s for the combined layout's single set. It is 1.6–1.9 times the combined layout and less than half the per-corner layout, which stores the table eight times, contracts 1,351 chunks against 169, and still misses deviations at the queried corner (Section 9.14). At the measured 0.092 ms per plaintext-ciphertext product the products themselves account for 16 ms in the combined and verified layouts and 125 ms in the per-corner layout, a computed figure; the rest is DPF evaluation and the Python-side encoding of one plaintext vector per chunk, which a native implementation largely avoids.

Table 5
Range aggregation against cube size, $d = 2$, combined layout, one template. Reference implementation, one thread.

Cells M	Chunks	DPF eval (ms)	Provider total (ms)
10,000	3	8.3	34.7
99,856	25	60.9	129.3
1,000,000	245	722.2	1356.0

Cost grows with the cube, linearly (Table 5): 34.7, 129.3 and 1,356.0 ms per provider for 10^4, about 10^5 and 10^6 cells, so cube size, not record count or range length, is the quantity a deployment provisions. The owner chooses which families form a cube, as it chooses templates.

Against the alternatives. The same query through single-tag aggregates, with each cell registered as its own tag, needs one query per cell in the box: 1,200 queries for a 240-minute window over five bands, each with its own keys and response, and the number of queries reveals the box's size. Through the flexible path it needs a retrieval for the device, each of the 240 minutes and each band before the contraction. A single server holding the same encrypted table needs no non-collusion assumption but an encrypted query as long as the table: 169 fresh ciphertexts in the combined layout, 44.4 MB of uplink computed from the measured ciphertext size, against 2.8 kB of DPF keys per provider, or 5.5 kB verified.

On the real corpora (Table 6). The second set of runs builds the cubes from the records themselves: device × one-minute window × CO band over the primary corpus, and site × day × $PM_{2.5}$ band over the second, with missing readings as an eleventh band. A query fixes one device or site, a window of L minutes or days and bands 3–7, and every answer matched the plaintext ground truth. Per provider a verified query costs 1.19 s on the primary cube ($M = 345{,}690$) and 0.68–0.77 s on the second ($M = 192{,}852$), and a combined-layout query 0.77–0.79 s and 0.44–0.48 s, with no trend in L from one window to the whole timeline. A box at the cube's origin, with seven dummy corners, costs the same (1,192.6 and 758.9 ms verified). Uplink is 5,520 B and 5,248 B per provider verified, half that combined, and every response is 132,081 B; a single server holding the same tables would need an encrypted query of 44.4 MB and 25.0 MB (computed). On both cubes the verified layout flagged all 250 tampered queries, fifty for each of the five deviations of Section 9.14, while the combined layout without a check flagged only the fifty inconsistent ones and returned the other 200 wrong answers unflagged. These runs used another machine than the synthetic ones (Section 8), so the two sets of latencies are not compared.

Table 6
Range aggregation per provider on cubes built from the real corpora, against window length L, $d = 3$, two templates. Reference implementation, one thread, AMD EPYC 7J13. Every query returns 132,081 B; uplink per provider is 2,760 and 2,624 B combined, 5,520 and 5,248 B verified.

L	Combined	Verified (session)	
	total (ms)	DPF eval (ms)	total (ms)
Primary corpus, device × minute × CO band: $3 \times 11{,}523 \times 10$, $M = 345{,}690$			
1 min	772.2	854.5	1188.9
60 min	787.3	850.5	1188.7
240 min	788.3	848.3	1185.8
1,440 min	767.8	870.4	1187.7
11,523 min	771.7	848.2	1189.6
Second corpus, site × day × $PM_{2.5}$ band: $12 \times 1{,}461 \times 11$, $M = 192{,}852$			
1 d	443.8	546.8	768.4
7 d	443.8	541.5	758.1
30 d	482.3	537.5	763.4
365 d	480.7	533.5	682.2
1,461 d	443.5	535.0	763.5

9.3. Selection latency and key size

Table 7 reports the per-provider full-domain evaluation in the C++ prototype, which is the whole of the symmetric-key selection. At $N = 11{,}580$ it costs 0.336 ms on one thread; at $N = 10^6$, 45.7 ms on one thread and 18.8 ms at thirty-two, beyond which it regresses as thread dispatch outweighs the per-level work. The two-party key grows from 266 B to 368 B, as $O(\lambda \log N)$ predicts. Sub-millisecond cells vary by up to 25% between runs, so only orders of magnitude are read from them: selection is not the bottleneck; the homomorphic contraction is.

Table 7
Per-provider selection latency and two-party key size against N. Medians of 21 runs.

N	Latency (ms), T threads					Key
	$T = 1$	4	16	32	64	(B)
1,000	0.032	0.032	0.032	0.032	0.032	198
10,000	0.290	0.175	0.156	0.161	0.183	266
11,580	0.336	0.200	0.177	0.181	0.211	266
100,000	4.418	2.487	1.909	1.928	2.420	317
10^6	45.741	25.701	19.711	18.769	24.401	368

9.4. Oblivious aggregation

In the C++ prototype the fast path costs 38.8–39.2 ms per provider across a 405× range of record counts, $N_d = 10^3$ to 405,184 (Table 8, Fig. 2); an earlier sweep in increasing N_d showed a warm-up step near 53 ms that vanished when the order was reversed. The single-round general path of Remark 1, whose $\Theta(NN_d)$ pass is the flexible path's first round, cost 103.7 ms at $N_d = 10^3$ and 1,378.2 ms at the full corpus, 35.5× the fast path, with an unpacked masked index of 37.5 GB per provider, which packing divides by 32. The two-ciphertext response, 525,950 B, was byte-identical for an empty posting list and one matching 4,999 of 5,000 records; packed and compressed it is 132,081 B.




Figure 2: Aggregate latency, fast path against the single-round general path (C++, two-ciphertext layout). The x-axis is N_d, not $|S|$: cost no longer depends on the matched-set size. The fast path is flat to $\pm 0.5\%$ over a $405\times$ range.

9.5. Comparison against baselines

Table 9 places the C++ fast path against the baselines on the primary corpus for a probe tag with the median $|S| = 35$. Plaintext scan and single-server searchable encryption are essentially free and leak everything or the access pattern and $|S|$; Path ORAM pays per matched record, so its cost and 373 kB downlink scale with $|S|$. The DORY-style search-only baseline costs 130.4 ms, 3.3× the fast path, because it materialises the selection vector the fast path never touches. The faithful homomorphic equality scan

Table 8
Aggregate latency and storage, fast path against the single-round general path, $N = 11{,}580$, template SUM, C++ prototype, two-ciphertext layout. Medians of 11 runs (fast) and 3 (general).

N_d	Fast (ms)	General (ms)	I' / provider (GB)	Downlink (B)
10^3	38.8	103.7	0.09	525,950
5×10^3	39.0	106.9	0.46	525,950
10^4	38.8	111.9	0.93	525,950
2×10^4	38.8	121.7	1.85	525,950
5×10^4	39.1	120.7	4.63	525,950
10^5	39.2	196.8	9.26	525,950
2×10^5	39.1	539.5	18.53	525,950
4.05×10^5	38.8	1,378.2	37.54	525,950

needs multiplicative depth 17 at ring dimension 32,768: 1.86 s per batch of 32,768 slots and 24.2 s per query, extrapolated, 617× the fast path. It is the right comparison for ad-hoc predicates on one server, and consistent with HADES's report that one-round homomorphic query processing over encrypted data takes more than fifteen hours for a million records, which HADES avoids only by evaluating predicates against plaintext data [34, §2.4]; for registered aggregates the stronger single-server alternative is baseline (vi), measured in Section 9.6.

Table 9
Baselines, same corpus and machine, $N_d = 10^5$, probe tag with the median $|S| = 35$. † marks an extrapolated value.

System	Server (ms)	Downlink (B)	Leakage to the server(s)
Plaintext scan	< 0.001	8	everything
SSE, 1 server	< 0.001	560	search and access pattern, $\lvert S\rvert$
Path ORAM	$0.059^{\dagger}$	373,248	$\lvert S\rvert$, via access count
DORY-style search	130.4	800,000	none; no analytics
FHE equality scan	$24{,}157^{\dagger}$	n/a	none; 1 server
CR-SHE, fast	**39.2**	**525,950**	class(q) only

9.6. Response packing, and what the trust split buys

Table 10 puts the two-ciphertext layout, the packed layout of Section 5.6, its compressed form and four-template responses through the reference implementation at both corpora's tag domains, together with baseline (vi), a single server holding the same encrypted columns. All rows come from one implementation on one machine and one thread, so they compare with each other and not with the C++ figures. Byte counts are a property of the parameters and of OpenFHE's serialisation, not of the machine; the C++ prototype's 262,975 B per ciphertext against 263,011 B here is a serialisation-version difference.

Packing halves the provider's work and the downlink. One rotate-and-sum over half-rows replaces two over full rows: a single template falls from 53.0 to 23.5 ms at $N = 11{,}580$ and from 55.8 to 31.4 ms at $N = 35{,}162$, and the response from two ciphertexts to one, 263,011 B, or 132,081 B compressed. Four templates in one compressed response cost 32.7 ms and 132,081 B at $N = 11{,}580$, against 194.9 ms and 2,104,088 B for four two-ciphertext responses (16× less downlink). At $N = 35{,}162$ they need 35 chunks instead of 12, so the cost grows to 74–92 ms while the response stays one ciphertext.

Table 10
Fast path per provider: two-ciphertext against packed layouts, and a single server on the same columns (baseline vi). Reference implementation, one thread; medians of 21 runs. k is the number of templates answered.

Layout	k	Provider (ms)	Downlink (B)
$N = 11{,}580$ *tags*			
Two ct (unpacked)	1	53.0	526,022
Packed, 1 ct	1	23.5	263,011
Packed + compressed	1	27.0	132,081
4× two ct	4	194.9	2,104,088
Packed, 1 ct	4	35.4	263,011
Packed + compressed	4	32.7	132,081
Single server (vi)	1	42.6	263,211
$N = 35{,}162$ *tags*			
Two ct (unpacked)	1	55.8	526,022
Packed, 1 ct	1	31.4	263,011
Packed + compressed	1	36.4	132,081
4× two ct	4	245.6	2,104,088
Packed, 1 ct	4	74.2	263,011
Packed + compressed	4	92.3	132,081
Single server (vi)	1	92.5	263,211

Against a single server, the trust split buys the client side. Baseline (vi) needs no non-collusion assumption. Its server costs 42.6 and 92.5 ms at the two tag domains, 1.8 and 2.9 times one packed CR-SHE provider (23.5 and 31.4 ms), because its contraction multiplies ciphertext by ciphertext; its response is the same one ciphertext. The ratios compare one provider with one server: two CR-SHE providers together spend 47.0 and 62.8 ms, so in total server work the trust split costs more than a single server at the smaller tag domain and saves about a third at the larger. Its query is not (Table 11): 789,033 and 2,367,099 B of fresh ciphertexts against a 260 or 294 B DPF key per provider (520 and 588 B in total for two), 3,035 and 8,051 times more uplink per provider, and 14.6 and 67.5 ms of client encryption against 0.54 and 0.62 ms of key generation. Query compression by ciphertext expansion [43] would cut that uplink to one ciphertext for more server automorphisms; we did not implement it.

Table 11
Per-query uplink and client cost: CR-SHE's two-party key against the single server's encrypted query. Reference implementation, one thread.

	Key (B)	Enc. query (B)	Cts	Encrypt (ms)
$N = 11{,}580$	260	789,033	3	14.6
$N = 35{,}162$	294	2,367,099	9	67.5

On retrieval a single server must bring every word of the packed $N \times \lceil N_d/32 \rceil$ index into contact with an encrypted one-hot query, about $\lceil N\lceil N_d/32\rceil/\ell \rceil$ plaintext-ciphertext products in a direct packed-selection formulation; query compression, preprocessing or specialised PIR layouts may change that. At the measured 0.092 ms per product this estimate is 81.6 ms at $N_d = 2 \times 10^4$ and 1.65 s at $N_d = 405{,}184$, against 26.0 ms and 1.10 s for CR-SHE's packed retrieval (Table 13); across the sweep the ratio is 1.5–3.1× for that cost model, not against a measured optimised single-server system, and the two figures come from separate runs. The separation on every single-keyword path is therefore a small constant factor in server work, set by a homomorphic slot operation (11 ns here) against a word operation, plus three orders of magnitude in uplink. That is the honest case for the non-collusion assumption on these paths: it pays where the client is thin or the link is metered, which is the IoT setting. On ranges (Section 9.2) the gap is wider.

9.7. The flexible path

Table 12 reports the two rounds of a flexible query at $N = 11{,}580$ in the reference implementation, swept in decreasing N_d to control for warm-up. Round one, the retrieval, grows linearly with N_d as its $\Theta(NN_d)$ contraction predicts. Round two costs 20.1–35.6 ms with no trend in N_d over this range, because one to five

packed products are dwarfed by the twelve rotations of the row sum, and it returns one 132,081 B ciphertext whatever the selection. Its uplink is a 16 B seed to $n-1$ providers and $8N_d$ B to one. Every flexible query in the reference implementation's tests, including conjunctions, disjunctions and ad-hoc weights, decrypts to the plaintext ground truth.

Table 12
Flexible path, $N = 11{,}580$, $n = 2$, reference implementation, one thread. Round-two uplink is the heavy provider's; the others receive 16 B.

N_d	Round 1 (ms)	Round 2 (ms)	Up (B)	Down (B)	I' (GB)
1,000	41.2	20.1	8,000	132,081	0.09
5,000	247.3	35.6	40,000	132,081	0.46
10,000	399.4	21.9	80,000	132,081	0.93
20,000	758.0	26.4	160,000	132,081	1.85

9.8. Packed masked index

Table 13 compares the masked index with one membership bit per $\mathbb{Z}_p$ word against 32 bits per word, at the primary corpus's tag domain $N = 11{,}580$, in the reference implementation. Packing divides the index by exactly 32 and makes retrieval 19 to 27 times faster at $N_d = 10^4$ and 2×10^4, where both layouts fit in this machine's memory. At the full 405,184 records the packed index is 1.17 GB, against 37.5 GB unpacked (computed), and a retrieval takes 1.10 s and returns 101,296 B per provider. Every retrieval returned exactly the posting list.

Table 13
Masked index, unpacked against 32 bits per word, $N = 11{,}580$. Reference implementation, one thread; retrieval per provider.

N_d	Layout	Index (GB)	Retrieval (ms)	Downlink (B)
10,000	unpacked	0.926	424.4	80,000
10,000	32 bits/word	0.029	22.0	2,504
20,000	unpacked	1.853	696.2	160,000
20,000	32 bits/word	0.058	26.0	5,000
100,000	32 bits/word	0.289	234.6	25,000
405,184	32 bits/word	1.173	1095.8	101,296

9.9. Multi-cloud deployment

With $n \in \{2, 3, 4\}$ separate provider processes and a client over TCP on one host (Table 14), provider compute is flat in n, at 34.82, 34.85 and 35.48 ms, so the client waits on the slowest provider, not on their sum. End-to-end latency rises from 44.1 to 52.5 ms, all of it transport of the n responses; the client's combine, verify and decrypt cost 1.37–1.63 ms. The transport covers loopback only: wide-area latency, bandwidth variation, stragglers and recovery were not measured, so no fixed cross-region increment can be inferred from these figures.

Table 14
Single-host deployment over loopback, medians of 100 queries. Transport excludes wide-area latency.

n	End-to-end (ms)	Provider (ms)	Transport (ms)	Client (ms)
2	44.12	34.82	8.30	1.37
3	45.40	34.85	9.09	1.52
4	52.53	35.48	15.48	1.63

9.10. Communication

At $N = 11{,}580$ the two-party construction sends a 266 B key to each provider, 532 B of uplink in total. The non-succinct n-party instantiation used for $n > 2$ sends 32 B to each of $n - 1$ providers and 92,656 B to one, so total uplink is 92,688 B at $n = 2$, 92,720 B at $n = 3$ and 92,752 B at $n = 4$. Tolerating more collusion is therefore nearly free in this instantiation, but moving beyond two providers at all costs a factor of 174 in uplink over the succinct two-party tree. A succinct $(n-1)$-private instantiation would reduce the heavy key from $O(N \log p)$ to $O(2^{n/2}\sqrt{N}\lambda)$.

Downlink is 525,950 B per provider for an aggregate in the two-ciphertext layout and 132,081 B packed and compressed, for up to four templates in our configuration, and a fixed $\lceil N_d/32 \rceil$ words for a retrieval, which is 25,000 B at $N_d = 10^5$ packed (800,000 B unpacked), none depending on $|S|$. A range query and a flexible round each return one 132,081 B ciphertext.

9.11. Leakage evaluation

We mount a frequency and volume leakage-abuse attack in the style of Islam et al. [9] and Cash et al. [10] against four representations of the index: unmasked, whose rows expose their Hamming weight and hence every posting-list length; padded to the next power of two; volume-hiding, every row padded to the longest; and the masked index of Section 5.4, whose row statistics are computed with the real PRF over all $N \times N_d$ entries. The adversary's auxiliary knowledge is the tag-frequency distribution of a similar deployment, modelled by binomially thinning the true posting lengths to a sampled fraction f of the records. It assigns each row to the tag of nearest auxiliary frequency, and a row counts as re-identified with weight $1/k$ when the true tag is among k equally near candidates, the expected success of breaking ties at random. The reference implementation ran the attack on both corpora at $f \in \{1, 0.5, 0.1, 0.01\}$ (Fig. 3, Table 15).




Figure 3: Share of tags re-identified against the adversary's auxiliary knowledge, four index representations, both corpora (log scales). The volume-hiding and masked curves coincide with random guessing. Table 15 breaks the $f = 1$ points down by class.

Unmasked, the index gives away the tags that carry meaning. Under perfect auxiliary knowledge the attack re-identifies every device, light-flag, motion-flag and temperature-band tag of the primary corpus, 92.5% of the humidity bands and 32.5% of the CO, LPG and smoke bands; on the second corpus, every wind direction and 95.5–100% of every pollutant, pressure and dew-point band, but only 33.3% of the sites. At $f = 1$ the auxiliary lengths are the true ones, so a tag is missed only when another tag has exactly the same posting length. Time buckets, of near-identical length, resist the attack (0.2% and 0.0%), and because they are most of the tag universe the overall rates are low, 0.484% and 0.324%, which is 56× and 114× random guessing.

Power-of-two padding helps but does not close the leak. It cuts overall recovery to 0.078% and 0.031%, still 9× and 11× random guessing, and leaves 55.6% of devices, 41.7% of light flags and 75.0% of motion

flags identifiable on the primary corpus and up to 18.3% of a band family on the second. With auxiliary knowledge thinned to $f = 0.01$, unmasked recovery falls to 0.082% and 0.055% and padded recovery to 0.052% and 0.022%, both still above random guessing.

Volume hiding and masking reduce the attack to guessing. Both give the random-guessing rate $1/N$ at every f on both corpora. Volume hiding pays for it in storage, inflating postings 1,285× on the primary corpus and 752× on the second ($N \max_x |I[x]|$ over the total postings, computed from the reference loader's statistics); the masked index costs a factor of 2 packed (Section 9.12). Masked row sums are spread over $\mathbb{Z}_p$, far beyond every auxiliary length, so the attack's guesses all fall on the tag with the longest posting list, which is therefore matched by default; that single tag is the 50.0% and 10.0% in the masked column of Table 15. In the C++ prototype the masked row statistics were not distinguishable from uniform over $\mathbb{Z}_p$ by a 64-bin chi-square test ($\chi^2 = 72.27$ on 63 degrees of freedom, $p_{\chi^2} = 0.198$, primary corpus; $\chi^2 = 62.38$, $p_{\chi^2} = 0.4986$, second corpus), empirical evidence for Theorem 1 rather than a proof of it.

Table 15
Tag re-identification by class under perfect auxiliary knowledge ($f = 1$), both corpora, reference implementation. Rates are the expected success of nearest-frequency assignment with random tie-breaking. In the masked column the attack's guesses all fall on the longest posting list, so one tag per corpus is matched by default.

Tag class	Unmasked	Power of two	Volume-hiding	Masked
Primary corpus				
Device	100.0%	55.6%	0.0%	0.0%
Light flag	100.0%	41.7%	0.0%	0.0%
Motion flag	100.0%	75.0%	0.0%	50.0%
CO band	32.5%	2.0%	0.0%	0.0%
LPG band	32.5%	2.0%	0.0%	0.0%
Smoke band	32.5%	2.0%	0.0%	0.0%
Humidity band	92.5%	2.0%	0.0%	0.0%
Temperature band	100.0%	11.8%	0.0%	0.0%
One-minute window	0.2%	0.0%	0.0%	0.0%
All tags	0.484%	0.078%	0.009%	0.009%
Random guessing		0.0086%		
Second corpus				
Site	33.3%	1.2%	0.0%	0.0%
Wind direction	100.0%	10.4%	0.0%	0.0%
$PM_{2.5}$ band	95.5%	3.3%	0.0%	0.0%
PM_{10} band	100.0%	5.6%	0.0%	0.0%
SO_2 band	100.0%	18.3%	0.0%	10.0%
NO_2 band	100.0%	3.3%	0.0%	0.0%
CO band	100.0%	3.0%	0.0%	0.0%
O_3 band	100.0%	12.2%	0.0%	0.0%
Pressure band	100.0%	10.2%	0.0%	0.0%
Dew-point band	95.5%	1.7%	0.0%	0.0%
Hour	0.0%	0.0%	0.0%	0.0%
All tags	0.324%	0.031%	0.003%	0.003%
Random guessing		0.0028%		

The C++ prototype's earlier figures are withdrawn. An earlier run of the attack in the C++ prototype reported higher unmasked recovery: 4.27% overall on the primary corpus, 100% in every non-temporal class of both corpora, 3.80% of one-minute windows and 0.31% of hourly windows. The last figure is not attainable by an attacker who sees only row statistics. Rows with the same observed statistic are indistinguishable to such an attacker, so whatever its strategy it expects at most one correct assignment per distinct value. An hourly window of the second corpus holds at most one record per site, so its posting length is one of at most twelve values, and at most twelve of the 35,046 hourly windows (0.034%) can be re-identified. The C++ attack must therefore have used information beyond the lengths, most plausibly an order of tied candidates that followed the true labels, and its 100% figures are suspect for the same reason. The two runs also used corpus builders that differ in band edges (Section 8). We report the reference figures, which the released code and data reproduce. The conclusion is unchanged and is now measured against the standard defences: an unmasked replicated index exposes the meaningful tag classes, power-of-two padding still exposes many

of them, and the masked index, like volume-hiding padding but without its storage cost, leaves the attack at random guessing.

9.12. Setup, masking and ingest costs

Unpacked, the mask costs a factor of 64 in index storage over a plaintext bitmap; packed, a factor of 2. In the C++ prototype the unpacked masked index at $N_d = 10^5$ took 5.6 s to build, the fast-path column A_f 1.2–12 ms per template, occupying 2 ciphertexts (0.53 MB) whatever N_d, and a complete provider bundle for the full corpus (context, evaluation keys, pk and eight columns) was 12 MB and took 0.8 s to produce. Insertion into the hot buffer ran at 4.5–14.1 million records per second; a fast-path static-tier rebuild cost 14.7–14.9 ms per template, 58.0 μs per insertion at $B = 256$ and 0.91 μs at $B = 16{,}384$, while the buffer scan added 98.8–100.0% to a query. The range cube registered in Section 9.2 took 1.3 s (combined) and 9.8 s (per-corner) to build and encrypt in the reference implementation.

9.13. Core scaling and throughput

In the C++ prototype a single fast-path query does not speed up with cores (34.3, 34.4 and 38.4 ms at 1, 8 and 64 threads), because the homomorphic contraction dominates, but throughput does: 29.1 queries/s with one client, 56.9 with two, 110.2 with four, and a plateau of 121.6–127.7 from sixteen to sixty-four clients, with median latency rising from 34.4 to 516 ms; between four and sixteen clients throughput is within 15% of its maximum and median latency stays under 135 ms.

9.14. Tamper evidence

Table 16 injects five provider deviations, 200 trials each, into every path and every verification mode of the reference implementation; one provider deviates and the other is honest. The last deviation is the strongest we can stage: the provider perturbs exactly the point the query reads, as if it knew the query. The fast path uses $N = 11{,}580$ tags, the range path a $3 \times 200 \times 10$ cube, the flexible round 4,096 records and retrieval a 512-tag index.

Table 16
Detected / undetected-and-wrong over 200 trials per cell, by path and verification mode. Columns: a constant added to the value slot; the share plus a uniform vector; the share scaled by k; the share plus $c\,u_x$ at a random point; the same at the point the query reads. Trials not counted were undetected and left the answer unchanged (the perturbed row was empty). Reference implementation.

Path	Check	Constant	Uniform	Scale	Random pt	Queried pt
Fast	one key	200/0	0/200	0/200	0/177	0/200
	per-row keys	200/0	200/0	200/0	182/0	0/200
	session	200/0	200/0	200/0	168/0	200/0
Range	one key	200/0	0/200	0/200	0/200	0/200
	per-cell keys	200/0	200/0	200/0	200/0	0/200
	session	200/0	200/0	200/0	200/0	200/0
Flexible	one key	200/0	0/200	0/200	0/200	0/200
	session	200/0	200/0	200/0	200/0	200/0
Retrieval	width check	0/200	200/0	200/0	200/0	200/0
	session	200/0	200/0	200/0	200/0	200/0

One stored key catches only the inconsistent constant: every consistent substitution, on every path, was accepted with a wrong answer, 0/200 detected in each cell. The C++ prototype gave the same 200/200 and 0/200 on the fast path. *Per-position keys* catch every deviation except the one aimed at the queried point, which passed 200 times out of 200 on the fast path and on the range path alike; they exist on neither the flexible path nor retrieval. *The session check* detected every deviation that changed the answer: across the 4,000 session trials on the four paths no wrong answer was accepted, and the 32 undetected fast-path trials perturbed an empty row, so their answers were correct. Retrieval without it relies on the four spare bits of each packed word, which catch any deviation that scrambles words but missed a single flipped membership bit in all 200 trials; the session check caught all of them.

9.15. Role-scoped access

Table 17 repeats the extraction attack of our earlier measurement, in which a client sending raw additive shares of basis vectors read every row of the masked index undetected (the C++ prototype recovered 512 of 512 rows). The reference deployment has 512 tags over three roles of 4,096 records each; the attacker holds role 0 and sends a raw share vector for every row. With one mask key it recovers every row exactly, including all 365,227 membership bits that belong to the other two roles. With role-scoped keys it recovers none of those bits and no row exactly; when it applies its own key to the other roles' words, 6.06% of them pass the width check, against the 6.25% expected of uniform words. Through the fast path the same user obtained, for all 512 tags, exactly the role-0 aggregate and in no case the all-role one, and a flexible round asking for every record returned the role-0 total. The price is storage: the aggregate columns, cube tables and record column are held once per role, while the masked index, the largest structure, is shared.

Table 17
Index extraction by a role-0 user sending raw shares for all 512 rows; three roles of 4,096 records. Reference implementation.

Index	Rows exact	Other roles' bits recovered	Other words pass width check
One mask key	512	365,227 of 365,227	n/a
Role-scoped keys	0	0 of 365,227	6.06%

9.16. Second corpus: twelve sites and a larger tag domain

The primary corpus has three devices, so its tag universe is dominated by time buckets. The C++ prototype therefore repeated every experiment above on the Beijing corpus, whose twelve sites give three times the tag domain ($N = 35{,}162$, posting lengths median 12, mean 131.5, maximum 102,344). Missing readings get their own `:na` tag rather than falling into the lowest band, since CO is missing in 4.92% of records, and temperature is shifted by $+50\,^{\circ}\mathrm{C}$ so that it stays non-negative. Every correctness check passed unchanged, including a byte-identical 525,950 B downlink for $|S| = 0$ and $|S| = 5{,}000$.

The fast path is unaffected by the larger tag domain. It cost 40.2–41.2 ms from $N_d = 5 \times 10^3$ to 4.05×10^5 (Table 18), 5% more than on the primary corpus for 3.04× the tags: the packed products grow from 2 ciphertexts to 5, but the fixed rotate-and-sum, encryption and serialisation dominate. The first point, 54.6 ms at $N_d = 10^3$, carries the warm-up artefact of Section 9.4, since this sweep ran in increasing N_d. *The unpacked masked index is storage-bound.* The general path cost 382.0 ms at $N_d = 10^5$ against 196.8 ms on the primary corpus, and its unpacked index grew to 28.13 GB; the harness refused the last two points, which needed 56.26 and 113.98 GB, against a 47.5 GB budget. Packing (Section 5.4) divides all of these by 32, to 3.6 GB at $N_d = 4.05 \times 10^5$ (computed).

Table 18
Second corpus ($N = 35{,}162$, N_d up to 420,370): aggregate latency and unpacked index size, template SUM, C++ prototype, two-ciphertext layout. Sweep in increasing N_d; "n/a" marks a point the harness refused on its memory budget.

N_d	Fast (ms)	General (ms)	I' (GB)	Downlink (B)
10^3	54.6	106.3	0.28	525,950
5×10^3	40.4	86.9	1.41	525,950
10^4	40.2	99.7	2.81	525,950
2×10^4	40.5	145.5	5.63	525,950
5×10^4	40.7	220.8	14.06	525,950
10^5	41.2	382.0	28.13	525,950
2×10^5	40.9	n/a	56.26	525,950
4.05×10^5	40.9	n/a	113.98	525,950

The leakage conclusion is not an artefact of three devices. On the second corpus too, the unmasked index exposes the wind directions and the pollutant, pressure and dew-point bands, and the masked index leaves the attack at random guessing (Section 9.11, Table 15).

The remaining measurements track the primary corpus. Provider compute in the single-host deployment was flat in n (38.67, 37.65 and 38.47 ms for $n = 2, 3, 4$), with end-to-end latency rising from 48.17 to 56.04 ms

in transport alone. The DORY-style search-only baseline cost 305.6 ms against 41.2 ms for the complete fast path, so the gap widens to 7.4× as N grows; the homomorphic equality scan, 24.4 s, is essentially unchanged, 592× the fast path. Throughput plateaued at 117–124 queries/s; insertion into the hot buffer ran at 4.5–11.1 million records per second; a fast-path static-tier rebuild cost 28.7–29.1 ms, twice the primary corpus and linear in N; and building the unpacked masked index at $N_d = 10^5$ took 16.6 s against 5.6 s, while A_f stays 5 ciphertexts (1.3 MB). Selection latency and keys depend on N alone and were not re-measured: the two-party key is 300 B and the n-party heavy key $8N + 16 = 281{,}312$ B, both computed.

9.17. Discussion

Ranges are where the design pays. A registered range aggregate costs the same for a one-minute window as for the whole timeline and returns one ciphertext; the single-tag path would need one query per cell, the flexible path one retrieval per tag, and a single server an encrypted query as long as the cube. On single-keyword aggregates one CR-SHE provider is 1.8–2.9 times faster than a single server holding the same columns, but two providers together are not, so the trust split's case rests on the client side: on ranges the uplink gap reaches four orders of magnitude, 5.5 kB verified against a computed 44 MB, which is the regime a thin IoT client is in.

Verification no longer costs a layout. With stored keys the choice was between the combined layout, cheap and unverifiable against consistent substitution, and the per-corner layout, eight times the storage and still blind to the queried corner. The per-query secret removes the trade: the verified layout keeps the combined layout's storage and homomorphic work, catches every deviation we injected that changed an answer, and costs one more full-domain evaluation per key.

Cube size is the provisioning knob. Range cost grows linearly in the number of cells, 1.36 s per provider at 10^6 cells in the combined layout of our unoptimised implementation. A deployment registers the cubes its analysts need, as it registers templates and roles, and the cell count, not the record count, bounds the per-query cost.

Retrieval is bounded by time, not storage. Packing brings the masked index from 37.5 to 1.17 GB per provider at the full primary corpus, so the flexible path, which serves arbitrary selections in two rounds, fits on commodity hosts.

9.18. Limitations

Evaluation. Range aggregation, session verification, role-scoped access and the packed index were measured in a single-threaded reference implementation, range aggregation on cubes built from both real corpora and the rest on synthetic data with the primary corpus's dimensions; none of them is in the C++ prototype, absolute latencies are those of an unoptimised driver, and figures are per provider. The C++ deployment ran over loopback on one host, so wide-area latency, bandwidth variation and stragglers were not measured. The C++ prototype's leakage figures are withdrawn (Section 9.11), and its corpus builder differs from the reference loader on the second corpus.

Expressiveness and updates. One-round range queries apply to registered data cubes and templates whose cumulative corpus total stays below p (a corpus-wide sum of squares requires a larger plaintext modulus p), while non-rectangular predicates and cross-cube conjunctions use the two-round flexible path.

Adversary. Privacy is proved for semi-honest providers and a trusted owner. Tamper evidence holds against arbitrary provider deviation but gives no output delivery, and a DU that reveals its aborts can leak up to one bit about the data per query. Role confinement assumes providers apply the policy and do not collude with users; it covers record partitions, not per-tag rights within a role.

Collusion beyond two providers. For $n > 2$ the prototype uses a non-succinct sharing whose heavy key is $8N + 16$ bytes; a range query needs 2^d such keys over the cube's M cells, twice that verified. Our key-size claims are for $n = 2$.

Prior art. Private aggregation, prefix-sum cubes and encrypted range aggregates are established topics, and Obscure is close on oblivious, verifiable, non-interactive aggregation. The 2^d box decomposition, the one-time-padded index and the client-chosen one-time MAC key each have a direct precursor [13, 17, 20]; what we offer is their combination in this setting. No system in Table 1 has been run against CR-SHE on the same data and hardware.

Multi-owner extensions. The construction assumes a single data owner and full delegation of decryption within each role; extending ingestion to multiple independent data owners via multi-key or threshold homomorphic encryption is a natural next step.

10. Conclusion

IoT analytics are range aggregates over time, place and value, and the data behind them increasingly sit encrypted across several clouds. CR-SHE answers such aggregates in one round, over data encrypted under one owner's key, hiding the range, the matched records, their number and the result from any coalition of up to $n-1$ providers that never talk to one another. Encrypted summed-area tables turn any box of a registered cube into 2^d point selections whose signs and dummy padding hide the box; oblivious homomorphic aggregation contracts each provider's share against encrypted columns so that the matched set is never assembled; a secret scalar drawn afresh for each query and carried in the keys makes any answer-changing deviation evident to the client at no extra homomorphic cost; and role-scoped columns and mask keys confine each user to its own records without interaction. At $t = n-1$ a homomorphic layer is our route to this, since a local additive-sharing alternative with data-independent queries would need single-server private retrieval. On two real IoT corpora a C++ prototype answers single-keyword aggregates in 39 ms per provider; on range cubes built from both corpora a reference implementation answers verified box queries in 0.68–1.19 s per provider with fixed-size 132 kB responses at flat cost across box lengths, and it accepted no wrong answer in 4,500 tampered session queries, leaked no other role's records under an index-extraction attack, and left a frequency attack at random guessing where power-of-two padding did not. A native port, cross-region latency and an outside review of the proofs come next. Future work will pursue sublinear preprocessing for dynamic streams, succinct multi-party DPF instantiations for $n > 2$, wide-area multi-region and edge-gateway evaluations, and multi-owner key management.

Declaration of competing interest

The authors declare that they have no known competing financial interests or personal relationships that could have appeared to influence the work reported in this paper.

Acknowledgements

This research did not receive any specific grant from funding agencies in the public, commercial, or not-for-profit sectors.

Data availability

Data will be made available on request.

Declaration of generative AI and AI-assisted technologies in the manuscript preparation process

During the preparation of this work the authors used three AI assistants. Claude (Anthropic) was used to convert the manuscript between journal templates, edit and restructure the text, write the plotting script that draws Fig. 1, develop the reference implementation with its tests and benchmark scripts, search the literature for prior work and compare the manuscript with papers the authors supplied, and draft parts of the text and analysis, including the range construction, the tamper-evidence mechanism with Theorem 2, role-scoped access with Proposition 2, and Sections 5.2, 5.10, 5.6, 9 and 10. ChatGPT (OpenAI) and Gemini (Google) were used to edit and review intermediate drafts; the framing, corrections, algorithm and proof refinements adopted from them were checked against the implementation and the measured results, and the per-record coupled MAC and role-blinded columns they proposed were reimplemented and measured before inclusion. No image was generated or altered by a generative AI tool. After using these tools, the authors reviewed and edited the content as needed and take full responsibility for the content of the publication.

References

[1] L. Atzori, A. Iera, G. Morabito, The Internet of Things: A survey, Computer Networks 54 (2010) 2787–2805.

[2] D. Petcu, Multi-cloud: Expectations and current approaches, in: Proc. Int. Workshop on Multi-Cloud Applications and Federated Clouds (MultiCloud), 2013, pp. 1–6.

[3] N. Grozev, R. Buyya, Inter-cloud architectures and application brokering: Taxonomy and survey, Software: Practice and Experience 44 (2014) 369–390.

[4] D. X. Song, D. Wagner, A. Perrig, Practical techniques for searches on encrypted data, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2000, pp. 44–55.

[5] R. Curtmola, J. Garay, S. Kamara, R. Ostrovsky, Searchable symmetric encryption: Improved definitions and efficient constructions, in: Proc. 13th ACM Conference on Computer and Communications Security (CCS), 2006, pp. 79–88.

[6] M. Islam, R. Palit, A keyword based searching and sharing scheme on the encrypted cloud data, in: 2023 14th International Conference on Computing Communication and Networking Technologies (ICCCNT), IEEE, 2023, pp. 1–6.

[7] J. Fan, F. Vercauteren, Somewhat practical fully homomorphic encryption, Cryptology ePrint Archive (2012).

[8] J. H. Cheon, A. Kim, M. Kim, Y. Song, Homomorphic encryption for arithmetic of approximate numbers, Cryptology ePrint Archive, Paper 2016/421, 2016. URL: https://eprint.iacr.org/2016/421.

[9] M. S. Islam, M. Kuzu, M. Kantarcioglu, Access pattern disclosure on searchable encryption: Ramification, attack and mitigation, in: Proc. Network and Distributed System Security Symposium (NDSS), 2012.

[10] D. Cash, P. Grubbs, J. Perry, T. Ristenpart, Leakage-abuse attacks against searchable encryption, in: Proc. 22nd ACM SIGSAC Conference on Computer and Communications Security (CCS), 2015, pp. 668–679.

[11] P. Grubbs, K. Sekniqi, V. Bindschaedler, M. Naveed, T. Ristenpart, Leakage-abuse attacks against order-revealing encryption, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2017, pp. 655–672.

[12] F. Wang, C. Yun, S. Goldwasser, V. Vaikuntanathan, M. Zaharia, Splinter: Practical private queries on public data, in: Proc. 14th USENIX Symposium on Networked Systems Design and Implementation (NSDI), 2017, pp. 299–313.

[13] E. Dauterman, E. Feng, E. Luo, R. A. Popa, I. Stoica, DORY: An encrypted search system with distributed trust, in: Proc. 14th USENIX Symposium on Operating Systems Design and Implementation (OSDI), 2020, pp. 1101–1119.

[14] E. Dauterman, M. Rathee, R. A. Popa, I. Stoica, Waldo: A private time-series database from function secret sharing, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2022.

[15] P. Gupta, et al., Obscure: Information-theoretic oblivious and verifiable aggregation queries, Proceedings of the VLDB Endowment (2019).

[16] P. Gupta, Y. Li, S. Mehrotra, N. Panwar, S. Sharma, S. Almanee, Obscure: Information-theoretically secure, oblivious, and verifiable aggregation queries on secret-shared outsourced data, IEEE Transactions on Knowledge and Data Engineering (2020).

[17] J. Li, L. F. Zhang, Silent guardians: Independent and secure decision tree evaluation without chatter, IEEE Transactions on Dependable and Secure Computing 23 (2026) 7691–7708.

[18] N. Gilboa, Y. Ishai, Distributed point functions and their applications, in: Annual International Conference on the Theory and Applications of Cryptographic Techniques, Springer, 2014, pp. 640–658.

[19] E. Boyle, N. Gilboa, Y. Ishai, Function secret sharing, in: Advances in Cryptology – EUROCRYPT 2015, volume 9057 of *LNCS*, Springer, 2015, pp. 337–367.

[20] E. Boyle, N. Gilboa, Y. Ishai, Function secret sharing: Improvements and extensions, in: Proceedings of the 2016 ACM SIGSAC conference on computer and communications security, 2016, pp. 1292–1303. doi:10.1145/2976749.2978429.

[21] S. Eskandarian, H. Corrigan-Gibbs, M. Zaharia, D. Boneh, Express: Lowering the cost of metadata-hiding communication with cryptographic privacy, in: Proc. 30th USENIX Security Symposium, 2021.

[22] H. Corrigan-Gibbs, D. Boneh, Prio: Private, robust, and scalable computation of aggregate statistics, in: Proc. 14th USENIX Symposium on Networked Systems Design and Implementation (NSDI), 2017, pp. 259–282.

[23] D. Boneh, E. Boyle, H. Corrigan-Gibbs, N. Gilboa, Y. Ishai, Lightweight techniques for private heavy hitters, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2021, pp. 762–776.

[24] S. Servan-Schreiber, S. Beyzerov, E. Yablon, H. Park, Private access control for function secret sharing, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2023.

[25] L. de Castro, A. Polychroniadou, Lightweight, maliciously secure verifiable function secret sharing, in: Advances in Cryptology – EUROCRYPT 2022, volume 13275 of *LNCS*, Springer, 2022.

[26] K. Storrier, A. Vadapalli, A. Lyons, R. Henry, Grotto: Screaming fast $(2+1)$-PC for $\mathbb{Z}_{2^n}$ via $(2,2)$-DPFs, in: Proc. ACM SIGSAC Conference on Computer and Communications Security (CCS), 2023.

[27] J. Doerner, a. shelat, Scaling ORAM for secure computation, in: Proc. ACM SIGSAC Conference on Computer and Communications Security (CCS), 2017.

[28] B. Chor, E. Kushilevitz, O. Goldreich, M. Sudan, Private information retrieval, Journal of the ACM 45 (1998) 965–981.

[29] A. Beimel, Y. Ishai, T. Malkin, Reducing the servers' computation in private information retrieval: PIR with preprocessing, in: Advances in Cryptology – CRYPTO 2000, volume 1880 of *LNCS*, Springer, 2000, pp. 55–73.

[30] C.-T. Ho, R. Agrawal, N. Megiddo, R. Srikant, Range queries in OLAP data cubes, in: Proceedings of the ACM SIGMOD International Conference on Management of Data, 1997, pp. 73–88.

[31] F. C. Crow, Summed-area tables for texture mapping, in: Proceedings of the 11th Annual Conference on Computer Graphics and Interactive Techniques (SIGGRAPH), 1984, pp. 207–212.

[32] Z. Espiritu, E. A. Markatou, R. Tamassia, Time- and space-efficient aggregate range queries over encrypted databases, Proceedings on Privacy Enhancing Technologies 2022 (2022) 684–704.

[33] I. Demertzis, et al., Practical private range search in depth, ACM Transactions on Database Systems (2018).
[34] X. Liu, N. Trieu, T. Gupta, I. Ahmad, D. Song, HADES: Range-filtered private aggregation on public data, Proceedings of the VLDB Endowment 18 (2025) 2159–.
[35] J. Hayata, J. C. N. Schuldt, G. Hanaoka, K. Matsuura, On private information retrieval supporting range queries, International Journal of Information Security 23 (2024) 629–647.
[36] S. M. Hafiz, C. Gupta, W. Wnuck, B. Vora, C.-N. Chuah, Private aggregate queries to untrusted databases, in: Network and Distributed System Security Symposium (NDSS), 2024.
[37] K. Ji, et al., Fine-grained policy constraints for distributed point function, IACR Cryptology ePrint Archive, 2023.
[38] A. R. Choudhuri, et al., Homomorphic secret sharing with verifiable evaluation, 2024.
[39] I. Damgård, V. Pastro, N. Smart, S. Zakarias, Multiparty computation from somewhat homomorphic encryption, in: Advances in Cryptology – CRYPTO 2012, volume 7417 of *LNCS*, 2012, pp. 643–662.
[40] H. Corrigan-Gibbs, D. Kogan, Private information retrieval with sublinear online time, in: Advances in Cryptology – EUROCRYPT 2020, LNCS, Springer, 2020.
[41] H. Corrigan-Gibbs, A. Henzinger, D. Kogan, Single-server private information retrieval with sublinear amortized time, in: Advances in Cryptology – EUROCRYPT 2022, LNCS, Springer, 2022.
[42] M. Zhou, A. Park, W. Zheng, E. Shi, Piano: Extremely simple, single-server PIR with sublinear server computation, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2024.
[43] S. Angel, H. Chen, K. Laine, S. Setty, PIR with compressed queries and amortized query processing, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2018.
[44] M. H. Mughees, H. Chen, L. Ren, OnionPIR: Response efficient single-server PIR, in: Proc. ACM SIGSAC Conference on Computer and Communications Security (CCS), 2021.
[45] S. J. Menon, D. J. Wu, Spiral: Fast, high-rate single-server PIR via FHE composition, in: Proc. IEEE Symposium on Security and Privacy (S&P), 2022.
[46] A. Davidson, G. Pestana, S. Celi, FrodoPIR: Simple, scalable, single-server private information retrieval, Proceedings on Privacy Enhancing Technologies 2023 (2023).
[47] E. Kushilevitz, R. Ostrovsky, Replication is not needed: Single database, computationally-private information retrieval, in: Proceedings of the 38th Annual Symposium on Foundations of Computer Science (FOCS), IEEE, 1997, pp. 364–373.
[48] O. Goldreich, R. Ostrovsky, Software protection and simulation on oblivious rams, Journal of the ACM (JACM) 43 (1996) 431–473.
[49] S. Kamara, T. Moataz, Computationally volume-hiding structured encryption, in: Advances in Cryptology – EUROCRYPT 2019, LNCS, Springer, 2019.
[50] S. Patel, G. Persiano, K. Yeo, M. Yung, Mitigating leakage in secure cloud-hosted data structures: Volume-hiding for multi-maps via hashing, in: Proc. ACM SIGSAC Conference on Computer and Communications Security (CCS), 2019.
[51] W. Xu, J. Zhang, Y. Yuan, Z. Li, Privacy-preserving multi-cloud based dynamic symmetric searchable encryption, in: 2021 2nd International Conference on Computer Communication and Network Security (CCNS), IEEE, 2021, pp. 176–181.
[52] W. Xu, J. Zhang, Y. Yuan, X. Wang, Symmetric searchable encryption with supporting search pattern and access pattern protection in multi-cloud, Concurrency and Computation: Practice and Experience 35 (2023) e7651.
[53] X. Zhang, C. Huang, Y. Su, J. Qin, Secure, dynamic, and efficient keyword search with flexible merging for cloud storage, IEEE Transactions on Services Computing 17 (2024) 2822–2835.
[54] N. Yang, C. Tang, Q. Zhou, D. He, Dynamic consensus committee-based for secure data sharing with authorized multi-receiver searchable encryption, IEEE Transactions on Information Forensics and Security 18 (2023) 5186–5199.
[55] R. Du, H. Jiang, M. Li, Lightweight searchable encryption with small clients on edge cloud, in: 2022 17th Asia Joint Conference on Information Security (AsiaJCIS), 2022, pp. 41–48. doi:10.1109/AsiaJCIS57030.2022.00017.
[56] S. Halder, T. Newe, Enabling secure time-series data sharing via homomorphic encryption in cloud-assisted iiot, Future Generation Computer Systems 133 (2022).
[57] A. Kamble, M. M. Jiet, C. Puri, Homomorphic encryption and its applications in multi-cloud security, in: 2024 International Conference on Inventive Computation Technologies (ICICT), IEEE, 2024, pp. 1493–1499.
[58] L. Burkhalter, A. Hithnawi, A. Viand, H. Shafagh, S. Ratnasamy, TimeCrypt: Encrypted data stream processing at scale with cryptographic access control, in: Proc. 17th USENIX Symposium on Networked Systems Design and Implementation (NSDI), 2020, pp. 835–850.
[59] L. Burkhalter, N. Küchler, A. Viand, H. Shafagh, A. Hithnawi, Zeph: Cryptographic enforcement of end-to-end data privacy, in: Proc. 15th USENIX Symposium on Operating Systems Design and Implementation (OSDI), 2021, pp. 387–404.
[60] C. Xu, N. Wang, L. Zhu, K. Sharif, C. Zhang, Achieving searchable and privacy-preserving data sharing for cloud-assisted e-healthcare system, IEEE Internet of Things Journal 6 (2019) 8345–8356.
[61] D. Wu, C. Nie, Z. Yang, P. Zhang, R. Wang, Distributed secure data sharing method for internet of vehicles based on homomorphic hash tree, IEEE Transactions on Vehicular Technology 73 (2024) 17572–17585.
[62] A. K. Verma, P. Patel, V. S. Bhatia, A. Rastogi, A. Prasad, P. Ranjan, Secure federated multi-party computation with homomorphic encryption and blockchain for preserving privacy in cloud storage of medical records, in: 2025 2nd International Conference on Intelligent Algorithms for Computational Intelligence Systems (IACIS), IEEE, 2025, pp. 1–6.
[63] N. Bharot, N. Mehta, J. G. Breslin, P. Verma, Cloudlock: secure data sharing using a hybrid cryptosystem in multi-cloud data storage, Cluster Computing 28 (2025) 464.
[64] S. Muthuvel, S. Priya, K. Kumar, Design of a multi-layered privacy-preserving architecture for secure medical data exchange in cloud environments, Scientific Reports 16 (2026).

[65] L. Wang, Z. Yang, X. Song, Shamc: A secure and highly available database system in multi-cloud environment, Future Generation Computer Systems 105 (2020) 873–883.
[66] D. Horkos, L. Perret, SoK: On cryptography for multi-cloud storage, Cryptology ePrint Archive, Paper 2026/207, 2026. URL: https://eprint.iacr.org/2026/207.
[67] R. Poddar, T. Boelter, R. A. Popa, Arx: An encrypted database using semantically secure encryption, Proceedings of the VLDB Endowment 12 (2019).
[68] N. Crooks, M. Burke, E. Cecchetti, S. Harel, R. Agarwal, L. Alvisi, Obladi: Oblivious serializable transactions in the cloud, in: Proc. 13th USENIX Symposium on Operating Systems Design and Implementation (OSDI), 2018.
[69] E. Dauterman, V. Fang, I. Demertzis, N. Crooks, R. A. Popa, Snoopy: Surpassing the scalability bottleneck in oblivious storage, in: Proc. 28th ACM Symposium on Operating Systems Principles (SOSP), 2021.
[70] O. Goldreich, S. Goldwasser, S. Micali, How to construct random functions, in: providing sound foundations for cryptography: On the Work of Shafi Goldwasser and Silvio Micali, 2019, pp. 241–264.
[71] G. Di Crescenzo, T. Malkin, R. Ostrovsky, Single database private information retrieval implies oblivious transfer, in: Advances in Cryptology – EUROCRYPT 2000, volume 1807 of *Lecture Notes in Computer Science*, Springer, 2000, pp. 122–138.
[72] S. Halevi, V. Shoup, Algorithms in HElib, in: Advances in Cryptology – CRYPTO 2014, volume 8616 of *Lecture Notes in Computer Science*, Springer, 2014, pp. 554–571.
[73] A. Al Badawi, J. Bates, F. Bergamaschi, D. B. Cousins, et al., OpenFHE: Open-source fully homomorphic encryption library, in: Proc. 10th Workshop on Encrypted Computing & Applied Homomorphic Cryptography (WAHC), 2022, pp. 53–63.
[74] G. A. Stafford, [dataset] environmental sensor telemetry data, Kaggle Datasets, 2020. Version 1.0. https://www.kaggle.com/datasets/garystafford/environmental-sensor-data-132k.
[75] S. Zhang, B. Guo, A. Dong, J. He, Z. Xu, S. X. Chen, Cautionary tales on air-quality improvement in Beijing, Proceedings of the Royal Society A 473 (2017) 20170457. Dataset: UCI Machine Learning Repository, Beijing Multi-Site Air-Quality Data, https://archive.ics.uci.edu/dataset/501.
[76] S. Chen, [dataset] Beijing multi-site air quality, UCI Machine Learning Repository, 2019. doi:10.24432/C5RK5G, https://doi.org/10.24432/C5RK5G.